

SEEDING SCHEDULE											
LOCATION	OFFSET LT / RT	SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	HEAVY DUTY EROSION CONTROL BLANKET	TEMP DITCH CHECKS	PERIMETER EROSION BARRIER	TEMP EROSION CONTROL SEEDING	INLET AND PIPE PROT.	TEMP FENCE •
STA TO STA		ACRE	POUND	POUND	POUND	SO YD	FOOT	FOOT	POUND	EACH	FOOT
243+00 TO 256+00	RT	1.4	126.0	126.0	126.0	6376.3	42.0	1329.8	280.0		
243+00 TO 256+50	MEDIAN	0.8	72.0	72.0	72.0	3486.8	42.0	0.0	160.0		
243+00 TO 256+50	LT	1.5	135.0	135.0	135.0	6785.0	42.0	1388.5	300.0		
265+00 TO 272+00	RT	0.8	72.0	72.0	72.0	3797.8	42.0	800.0	160.0		97.6
265+30 TO 272+00	MEDIAN	0.4	36.0	36.0	36.0	1708.3	42.0	0.0	80.0		
266+00 TO 273+30	LT	0.8	72.0	72.0	72.0	3829.6	42.0	826.3	160.0		99.1
252+31	MEDIAN									1.0	
270+00	MEDIAN									1.0	
GRAND TOTAL		6	513	513	513	25984	252	4345	1140	2	197

• NOTE: Temporary fence to be placed at each end of pedestrian box culvert as shown on plans. See Special Provisions.

EARTH EXCAVATION SCHEDULE						
(1) STA TO STA	(2) EARTH EX	(3) EARTH EX ADJ FOR SHRINKAGE	(4) EMBANK	(5) EARTHWORK BAL WASTE(+) OR SHORTAGE(-)		
	LANE	CU YD	CU YD	CU YD	CU YD	CU YD
STA 243+00 TO STA 273+00	NB/SB/MED	1703	1277	7605	-6328	
GRAND TOTALS		1703	1277	7605	-6328	

COLUMNS 2, AND 4-LOCATION AND QUANTITIES FROM CROSS SECTIONS
 COLUMN 3- QUANTITY OF EARTH EXCAVATION (CUT) ADJUSTED FOR A SHRINKAGE FACTOR OF 25% (1- SHRINKAGE FACTOR)
 COLUMN 5 EARTHWORK REQUIRED (PAY FOR AS FINISHED EXCAVATION)

STA 256+74 TO STA 265+05 ARE OMITTED FROM ABOVE QUANTITIES FOR BRIDGES LOCATION.

NOTE ALL MATERIAL EXCAVATED ON THIS PROJECT MUST BE USED AS FILL. NO MATERIAL WILL BE ALLOWED TO BE REMOVED

TREE REMOVAL SCHEDULE			
STATION	DISTANCE	AVERAGE DISTANCE FROM EDGE OF SHOULDER TO R.O.W. LINE*	TREE REMOVAL ACRES
	FEET	FEET	ACRES
NORTHBOUND OUTSIDE			
253+25 TO 256+71	346	49.5	0.39
265+78 TO 268+60	282	60	0.39
SOUTHBOUND OUTSIDE			
252+75 TO 256+00	325	47.5	0.35
264+65 TO 267+80	315	60	0.43
TOTAL			1.57

*PAY WIDTH OF TREE REMOVAL (ACRES) MEASURED FROM EDGE OF OUTSIDE SHOULDER TO ROW LINE

FENCE SCHEDULE					
LOCATION (APPROXIMATE LOCATIONS)	NB SB	CHAIN LINK FENCE 6'	CHAIN LINK FENCE REMOVAL	WOVEN WIRE FENCE 4'	WOVEN WIRE FENCE REMOVAL
STATION		FT	FT	FT	FT
254+92 TO 256+15	SB	130	130		
256+22 TO 256+75	NB	74	74		
250+00 TO 254+92	SB			492	492
264+14 TO 266+86	SB			341	341
265+86 TO 266+84	NB			173	173
267+06 TO 271+00	NB			449	449
267+09 TO 271+00	SB			438	438
STAGE I 267+00 EAST AND WEST ROW*				30	
STAGE II 267+00 EAST AND WEST ROW*				30	
TOTAL		204	204	1953	1893

*THIS IS FOR THE CLOSURE OF THE PEDESTRIAN WALKWAY DURING STAGE I AND II CONSTRUCTION OF THE BOX CULVERT.