

STAGE CONSTRUCTION ITEMS										
LOCATION	STA	LENGTH	TEMPORARY CONCRETE BARRIER FOOT	TEMP MODULAR GLARE SCREENS(4) FOOT	RELOCATE TEMP CONC BARRIER, SP (5) FOOT	TBT, T1 (SPECIAL) TANGENT(1) EACH	WORK ZONE PVT MK REMOVAL(2) SQ FT	PAVEMENT MARKING REMOVAL(3) SQ FT	PAVEMENT MARKING TAPE, TYPE IV, 4"	
									WHITE FOOT	YELLOW FOOT
STAGE I										
NBL	237+00 TO 280+72(CL AND WHITE EDGE LN)	4372					2911.8	4372.0	4372.0	4372.0
	267+50 TO 268+00	50				1				
SBL	235+00+00 TO 278+00(CL ONLY)	4300					1419	1075.0		4300.0
STAGE II										
NBL	235+00 TO 280+72 (CL ONLY)	4572					1509	1143.0		4572.0
SBL	236+00 TO 280+72(CL AND EDGE LN)	4472					2591	4472	4472.0	4472.0
	253+50 TO 254+00 (SBL)	50				1				
	STAGE I 235+68 TO 281+72	4605	3815	3815	1580					
	STAGE II 234+00 TO 280+72	4671	3880	3880	1580					
GRAND TOTALS			7695.0	7695.0	3160.0	2.0	8430.8	11062.0	8844.0	17716.0

*OVERALL LENGTH INCLUDES LENGTH TO REMOVE EXISTING CENTERLINE PVT MK
(1) PLACE TBT, TYPE I SPECIAL (TANG) PRIOR TO EACH STAGE IN THE PL
(2) WK ZONE PVT MK REMOVAL IS TO REMOVE THE PAVEMENT MARKING TAPE, TYPE IV PLACED AFTER STAGE I AND STAGE II CONSTRUCTION
(3) PAVEMENT MARKING REMOVAL IS TO REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO STAGE I AND STAGE II CONSTRUCTION
(4) GLARE SCREENS TO BE USED DURING STAGE I AND STAGE II CONSTRUCTION
(5) RELOCATE TEMP CONCRETE BARRIER THAT IS CURRENTLY IN THE NORTH MEDIAN CROSSOVER TO THE LOCATIONS SHOWN IN STAGE I.
FOUR MOVES NECESSARY, 790' PER MOVE- ONE PRESTAGE I, ONE POST STAGE I, ONE PRESTAGE II, ONE POST STAGE II-SEE SPECIAL PROVISIONS

IMPACT ATTENUATOR SCHEDULE		
STA TO STA	LANE	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3
		EACH
STA. 242+85 TO 243+15	MEDIAN	1
GRAND TOTALS		1