



LEGEND	
	TEMPORARY DITCH CHECK
	PERIMETER EROSION BARRIER
	TEMPORARY EROSION CONTROL SEEDING, EROSION CONTROL BLANKET AND SEEDING CLASS 2A
	STONE RIPRAP, CLASS A4 & FILTER FABRIC
	LIMITS OF CONSTRUCTION
	TEMPORARY FENCE

**NOTES:**

1. ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE CONSTRUCTED WITHIN THE RIGHT-OF-WAY OR TEMPORARY EASEMENT.
2. ALL SEDIMENT AND EROSION CONTROL SYSTEMS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EACH 1/2" OR GREATER RAIN EVENT.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EROSION CONTROL</b>		F.A.I. RTE. 57	SECTION (140)BR, BR-1 & (1)	COUNTY KANKAKEE	TOTAL SHEETS 183	SHEET NO. 38	
#MODELNAME#	PLOT SCALE = #SCALE#	CHECKED - _____	REVISED - _____		SCALE: _____	SHEET _____	OF _____	SHEETS	STA. _____	TO STA. _____	<b>CONTRACT NO. 66750</b>	
	PLOT DATE = #DATE#	DATE - _____	REVISED - _____		ILLINOIS FED. AID PROJECT							