

90% FED. / 10% STATE

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY 0004 URBAN	BRIDGE 0011 046-0003	BRIDGE 0011 046-0004	BOX CULVERT 0040 046-2552
* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4				4
* 81603045	UNIT DUCT, 600V, 3-1/C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	500				500
* 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	910				910
* 81702417	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6, 1/C NO. 6 GROUND	FOOT	1070				1070
* X8211150	LUMINAIRE, LED, CEILING MOUNT, 50 WATT	EACH	6				6
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YDS	3300	3300			
54200217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	46	46			
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	80	80			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2			
X0326208	ALTERNATE ROUTE SIGNING	L SUM	1	1			
X0326649	LINEAR DELINEATOR PANELS, 6 INCH	EACH	28	28			
X0326867	RADAR SPEED TRAILER	CAL MO	26	26			
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOURL	1600	1600			
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	13	13			
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	21858	21858			
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6489	6489			

FILE NAME *	USER NAME * #USER*	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - _____	REVISED - _____					57	1140BR, BR-1 & 111	KANKAKEE	183	11
#MODELNAME*	PLOT SCALE * #SCALE*	CHECKED - _____	REVISED - _____		SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66750				
	PLOT DATE * #DATE*	DATE - _____	REVISED - _____		ILLINOIS FED. AID PROJECT							

Rev.