

FENCING & SIGNS SCHEDULE

LOCATION	STATION	OFFSET	STATION	OFFSET	SIGN TYPE	REM & REIN DELINEATOR (EACH)	WOV W FENCE 4 (FOOT)	REMOV SIGN PANEL T1 (SQ FT)	REMOV SIGN PANEL T2 (SQ FT)	SIGN PANEL T1 (SQ FT)	SIGN PANEL T2 (SQ FT)	WOOD SIN SUPPORT (FOOT)	MILE POST MKR ASSEMBLY (EACH)
I-80 EB													
EB XOVER	396+60					1							
EB XOVER	404+60					1							
	407+40	44' LT			"NO U TURN" R3-4-3636					9		17	
	407+40	44' LT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624					6			
EXISTING "HENNEPIN CANAL" SIGN	428+31	25.7' RT			"HENNEPIN CANAL" D7-1-4830			10		10		15	
"MILE MARKER 44"	428+31	25.7' RT											1
	428+50	RT	435+60	RT		2							
EXISTING SIGN	432+23	43.5' LT			"NO U TURN" R3-4-3636			9					
EXISTING SIGN	432+23	43.5' LT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624			6					
EXISTING SIGN	432+23	43.5' LT			"NO U TURN" R3-4-3636			9					
EXISTING SIGN	432+23	43.5' LT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624			6					
	439+95	44' LT			"NO U TURN" R3-4-3636					9		17	
	439+95	44' LT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624					6			
I-80 WB													
	409+37	44' RT			"NO U TURN" R3-4-3636					9		17	
	409+37	44' RT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624					6			
WB XOVER	412+15					1							
WB XOVER	420+15					1							
EXISTING "HENNEPIN CANAL" SIGN	426+43	28.5' LT			"HENNEPIN CANAL" D7-1-4830			10		10		15	
"MILE MARKER 44"	428+04	25.3' LT											1
	428+50	LT	435+60	LT		2							
	442+06	44' RT			"NO U TURN" R3-4-3636					9		17	
	442+06	44' RT			"EXCEPT AUTHORIZED VEHICLES" R3-1101-3624					6			
HENNEPIN CANAL													
WEST CANAL BANK							93						
EAST CANAL BANK							218						
TOTAL						8	311	30	20	60	20	98	2