

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	BRIDGE				
				0004	0011				
28100705	STONE DUMPED RIPRAP, CLASS A3	SO YD	401	12	389				
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	296		296				
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	5,619	5,619					
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SO YD	215	215					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	815	815					
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2,502	2,502					
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1,925	1,925					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	5,337	5,337					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	78	78					
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	3,884	3,884					
44000100	PAVEMENT REMOVAL	SO YD	776	776					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	14,577	14,577					
44004250	PAVED SHOULDER REMOVAL	SO YD	3,554	3,554					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,172	1,172					

\* SPECIALTY ITEMS