

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	BRIDGE		
				0004	0011		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,058	1,058			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		2		
50157300	PROTECTIVE SHIELD	SQ YD	1,227		1,227		
50200100	STRUCTURE EXCAVATION	CU YD	951		951		
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	265		265		
50300225	CONCRETE STRUCTURES	CU YD	294.0		294.0		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,008.0		1,008.0		
50300260	BRIDGE DECK GROOVING	SQ YD	2,373		2,373		
50300300	PROTECTIVE COAT	SQ YD	2,846		2,846		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	10,620		10,620		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	299,740		299,740		
51100100	SLOPE WALL 4 INCH	SQ YD	510		510		
51200700	FURNISHING PRECAST CONCRETE PILES 14"	FOOT	2,208		2,208		

\* SPECIALTY ITEMS

FILE NAME = 0366998-shl-500.dgn	USER NAME = brianhess PLOT TIME = 7:18:16 PM PLOT SCALE = 100.0000' / 1" = PLOT DATE = 7/30/2013	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: SHEET 3 OF 8 SHEETS STA. TO STA.	F.A.I. RTE. 80	SECTION (06-2) BR-3,4	COUNTY BUREAU	TOTAL SHEETS 133	SHEET NO. 5	CONTRACT NO. 66998 ILLINOIS FED. AID PROJECT
------------------------------------	---	--	--	---	--	----------------------	--------------------------	------------------	---------------------	----------------	---