

80% FED. / 20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BOX CULVERT
				0004	0011 S.N. 050-2651
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30	
20200100	EARTH EXCAVATION	CU YD	184	184	
20400800	FURNISHED EXCAVATION	CU YD	381	381	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	661		661
25000300	SEEDING, CLASS 3	ACRE	0.9	0.9	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	4356	4356	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	180	180	
28000305	TEMPORARY DITCH CHECKS	FOOT	80	80	
28000400	PERIMETER EROSION BARRIER	FOOT	560	560	
28100107	STONE RIPRAP, CLASS A4	SQ YD	210		210
28200200	FILTER FABRIC	SQ YD	210		210

14

FILE NAME : c:\p\work\p\pidot\plotsch\d0249716\0366813-ah\soq.dgn	USER NAME : plotsch	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 311	SECTION (4)BR-1	COUNTY LASALLE	TOTAL SHEETS 38	SHEET NO. 3
PLOT SCALE : 100.0000' / 1" =	CHECKED - _____	REVISED - _____	REVISED - _____		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT CONTRACT NO. 66B13					
PLOT DATE : 8/2/2013	DATE - _____	REVISED - _____	REVISED - _____										