



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 25, 2013

SUBJECT: FAP Route 326(IL 47)  
Project ACNCII-0326(088)  
Section (110) R, BR & BR-1  
Grundy & Kendall Counties  
Contract No. 66B83  
Item No. 33, November 8, 2013 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages 90- 91 of the Special Provisions.
3. Revised Plans sheets No. 4 & 42

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Paul Loete, Region 2, District 3; N. R. Stoner; Dave Lippert, Tim Kell; D. Carl Puzey; Estimates

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0320374	PLUG EX SAN SEWERS	EACH	1.000				
X0324159	WHITEWASH CONC PAVT	SQ YD	179,811.000				
X0325279	CLASS SI CONC (MISC)	CU YD	6.300				
X0325667	WD CTRL MWNG STRP SP	SQ YD	895.000				
X0326020	UTILTY PROTECTION PAD	SQ YD	1,743.000				
X0327420	SAN SEWER DI 8	FOOT	25.000				
X0327651	WAT MN IN CASING 12	FOOT	1,115.000				
X4060110	BIT MATLS PR CT	POUND	120,764.000				
X4401198	HMA SURF REM VAR DP	SQ YD	1,469.000				
X4402800	ISLAND PAVEMENT REM	SQ YD	23.000				
X5860110	GRANULAR BACKFILL STR	CU YD	1,243.000				
X6013600	PIPE UNDERDRAIN 4 MOD	FOOT	89,070.000				
X6022820	MAN SAN 5 DIA T1F CL	EACH	1.000				
X6022850	MAN SAN 8 DIA T1F CL	EA	2.000				
X6022855	MAN SAN 9 DIA T1F CL	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6026054	SAN MAN REMOVED	EACH	6.000				
X6026056	SAN MH ADJ NEW T1F CL	EACH	5.000				
X6026057	SAN MH REC NEW T1F CL	EACH	1.000				
X6026632	VALVE BOX REMOVED	EACH	15.000				
X6061100	CONC MED TSB SPL	SQ FT	15,826.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7830070	GRV RCSD PVT MRKG 5	FOOT	96,169.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	12,038.000				
X7830076	GRV RCSD PVT MRKG 9	FOOT	12,686.000				
X8410102	TEMP LIGHTING SYSTEM	L SUM	1.000				
X8410118	MAINT TEMP LIGHT SYS	L SUM	1.000				
X8570226	FAC T4 CAB SPL	EACH	1.000				
X8570231	FAC T5 CAB SPL	EACH	1.000				
X8730250	ELCBL C 20 3C TW SH	FOOT	1,370.000				
X8860100	LOOP DET TESTING	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0013302	SEGMENT CONC BLK WALL	SQ FT	125.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018400	DRAINAGE STR ADJ	EACH	1.000				
Z0018700	DRAINAGE STR REMOVED	EACH	19.000				
Z0023602	GRAN CULVERT BACKFILL	CU YD	1,235.000				
Z0029652	HT CBL MEDIAN BARRIER	FOOT	1,700.000				
Z0029653	HT CBL MED BAR DEMO	EACH	2.000				
Z0029654	HT CBL MED BAR TERM	EACH	6.000				
Z0030850	TEMP INFO SIGNING	SQ FT	149.500				
Z0032900	LAND SECTION MARKERS	EACH	11.000				
Z0033056	OPTIM TRAF SIGNAL SYS	EACH	1.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	690.000				
Z0056608	STORM SEW WM REQ 12	FOOT	510.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0056610	STORM SEW WM REQ 15	FOOT	466.000				
Z0056612	STORM SEW WM REQ 18	FOOT	82.000				
Z0056616	STORM SEW WM REQ 24	FOOT	293.000				
Z0056620	STORM SEW WM REQ 30	FOOT	142.000				
Z0056800	SAN SEW 6	FOOT	20.000				
Z0062456	TEMP PAVEMENT	SQ YD	13,328.000				
Z0065767	SLOT DR 15"W/1.75" SL	FOOT	419.000				
Z0073002	TEMP SOIL RETEN SYSTM	SQ FT	1,253.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	1.000				
Z0076600	TRAINEES	HOUR	2,500.000		0.800		2,000.000
Z0076604	TRAINEES TPG	HOUR	2,500.000		10.000		25,000.000
20100110	TREE REMOV 6-15	UNIT	2,917.000				
20100210	TREE REMOV OVER 15	UNIT	1,710.000				
20101000	TEMPORARY FENCE	FOOT	3,002.000				
*REV 20200100	EARTH EXCAVATION	CU YD	71,108.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20200200	ROCK EXCAVATION	CU YD	570.000				
20201200	REM & DISP UNS MATL	CU YD	86,043.000				
20300100	CHANNEL EXCAVATION	CU YD	2,860.000				
*REV 20400800	FURNISHED EXCAVATION	CU YD	276,120.000				
20700220	POROUS GRAN EMBANK	CU YD	289.000				
20800150	TRENCH BACKFILL	CU YD	3,352.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	40,469.000				
21101505	TOPSOIL EXC & PLAC	CU YD	30,318.000				
21301052	EXPLOR TRENCH 52	FOOT	43,821.000				
25000210	SEEDING CL 2A	ACRE	44.750				
25000310	SEEDING CL 4	ACRE	17.250				
25000400	NITROGEN FERT NUTR	POUND	5,671.000				
25000500	PHOSPHORUS FERT NUTR	POUND	5,671.000				
25000600	POTASSIUM FERT NUTR	POUND	5,671.000				
25100115	MULCH METHOD 2	ACRE	103.250				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25100630	EROSION CONTR BLANKET	SQ YD	136,556.000				
25200110	SODDING SALT TOLERANT	SQ YD	9,405.000				
25200200	SUPPLE WATERING	UNIT	140.000				
28000250	TEMP EROS CONTR SEED	POUND	6,996.000				
28000305	TEMP DITCH CHECKS	FOOT	12,769.000				
28000400	PERIMETER EROS BAR	FOOT	13,415.000				
28000500	INLET & PIPE PROTECT	EACH	132.000				
28100105	STONE RIPRAP CL A3	SQ YD	26.000				
28100107	STONE RIPRAP CL A4	SQ YD	3,324.000				
28200200	FILTER FABRIC	SQ YD	3,350.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	221,914.000				
30300118	AGG SUBGRADE IMPR 18	SQ YD	34,690.000				
31100500	SUB GRAN MAT A 6	SQ YD	9,340.000				
31100700	SUB GRAN MAT A 8	SQ YD	2,499.000				
31100910	SUB GRAN MAT A 12	SQ YD	5,780.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
31101200	SUB GRAN MAT B 4	SQ YD	114.000				
31101900	SUB GRAN MAT C	TON	28,720.000				
31200100	STAB SUBBASE 4	SQ YD	179,811.000				
35101600	AGG BASE CSE B 4	SQ YD	3,133.000				
35101800	AGG BASE CSE B 6	SQ YD	2,675.000				
35600722	HMA BC WID 11 1/2	SQ YD	27.000				
40200800	AGG SURF CSE B	TON	1,692.000				
40201000	AGGREGATE-TEMP ACCESS	TON	4,263.000				
40600645	LEV BIND MM N90	TON	87.000				
40600990	TEMPORARY RAMP	SQ YD	51.000				
40603085	HMA BC IL-19.0 N70	TON	5,970.000				
40603090	HMA BC IL-19.0 N90	TON	4,495.000				
40603340	HMA SC "D" N70	TON	1,889.000				
40603345	HMA SC "D" N90	TON	1,144.000				
40800050	INCIDENTAL HMA SURF	TON	2,102.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42000511	PCC PVT 10 1/2 JOINTD	SQ YD	158,379.000				
42001200	PAVEMENT FABRIC	SQ YD	40.000				
42001300	PROTECTIVE COAT	SQ YD	244,751.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	1,067.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	86.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	5,487.000				
42400100	PC CONC SIDEWALK 4	SQ FT	7,307.000				
42400800	DETECTABLE WARNINGS	SQ FT	120.000				
44000100	PAVEMENT REM	SQ YD	83,606.000				
44000159	HMA SURF REM 2 1/2	SQ YD	621.000				
44000200	DRIVE PAVEMENT REM	SQ YD	3,862.000				
44000500	COMB CURB GUTTER REM	FOOT	1,005.000				
44000600	SIDEWALK REM	SQ FT	2,427.000				
44004250	PAVED SHLD REMOVAL	SQ YD	21,821.000				
48101200	AGGREGATE SHLDS B	TON	5,233.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48203021	HMA SHOULDERS 6	SQ YD	2,317.000				
48300300	PCC SHOULDERS 8	SQ YD	58,813.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				
50100600	REM EXIST STRUCT N4	EACH	1.000				
50100700	REM EXIST STRUCT N5	EACH	1.000				
50100800	REM EXIST STRUCT N6	EACH	1.000				
50100900	REM EXIST STRUCT N7	EACH	1.000				
50101000	REM EXIST STRUCT N8	EACH	1.000				
50101100	REM EXIST STRUCT N9	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	2,499.000				
50200100	STRUCTURE EXCAVATION	CU YD	1,890.000				
50300100	FLOOR DRAINS	EACH	10.000				
50300225	CONC STRUCT	CU YD	490.400				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300255	CONC SUP-STR	CU YD	1,856.200				
50300260	BR DECK GROOVING	SQ YD	2,653.000				
50300300	PROTECTIVE COAT	SQ YD	4,027.000				
50400735	F&E PPC BULB T-BM 63	FOOT	1,399.000				
50401105	F & E P P CON I-BM 54	FOOT	1,473.500				
50800105	REINFORCEMENT BARS	POUND	21,760.000				
50800205	REINF BARS, EPOXY CTD	POUND	410,660.000				
50800515	BAR SPLICERS	EACH	1,145.000				
50900805	PEDESTRIAN RAIL	FOOT	24.000				
51201610	FUR STL PILE HP12X63	FOOT	1,717.000				
51201800	FUR STL PILE HP14X73	FOOT	1,475.000				
51202305	DRIVING PILES	FOOT	3,192.000				
51203610	TEST PILE ST HP12X63	EACH	1.000				
51203800	TEST PILE ST HP14X73	EACH	2.000				
51204650	PILE SHOES	EACH	77.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51500100	NAME PLATES	EACH	10.000				
54003000	CONC BOX CUL	CU YD	118.600				
54010503	PCBC 5X3	FOOT	910.000				
54010704	PCBC 7X4	FOOT	386.000				
54010804	PCBC 8X4	FOOT	176.500				
542A0220	P CUL CL A 1 15	FOOT	49.000				
542A0229	P CUL CL A 1 24	FOOT	60.000				
542A0241	P CUL CL A 1 36	FOOT	392.000				
542A0247	P CUL CL A 1 42	FOOT	567.000				
542A5482	P CUL CL A 1 EQRS 27	FOOT	249.000				
542A5485	P CUL CL A 1 EQRS 30	FOOT	100.000				
542A5503	P CUL CL A 1 EQRS 48	FOOT	216.000				
542D0220	P CUL CL D 1 15	FOOT	739.000				
542D0223	P CUL CL D 1 18	FOOT	531.000				
542D0226	P CUL CL D 1 21	FOOT	45.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542D0229	P CUL CL D 1 24	FOOT	164.000				
542D0235	P CUL CL D 1 30	FOOT	62.000				
542D0241	P CUL CL D 1 36	FOOT	100.000				
542D5473	P CUL CL D 1 EQRS 18	FOOT	27.000				
5421A015	P CUL CL A 1 15 TEMP	FOOT	304.000				
5421A018	P CUL CL A 1 18 TEMP	FOOT	192.000				
5421A030	P CUL CL A 1 30 TEMP	FOOT	40.000				
54213657	PRC FLAR END SEC 12	EACH	88.000				
54213660	PRC FLAR END SEC 15	EACH	6.000				
54213663	PRC FLAR END SEC 18	EACH	5.000				
54213669	PRC FLAR END SEC 24	EACH	8.000				
54213675	PRC FLAR END SEC 30	EACH	3.000				
54213693	PRC FLAR END SEC 48	EACH	2.000				
54214512	PRC FL END S EQ RS 27	EACH	8.000				
54214515	PRC FL END S EQ RS 30	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54215550	MET END SEC 15	EACH	31.000				
54215553	MET END SEC 18	EACH	16.000				
54215556	MET END SEC 21	EACH	2.000				
54215559	MET END SEC 24	EACH	4.000				
54215565	MET END SEC 30	EACH	2.000				
54215571	MET END SEC 36	EACH	2.000				
54215763	MET END SEC EQV RS 18	EACH	2.000				
54260311	TRAVERS PIPE GRATE	FOOT	786.000				
54261436	CONC ES 542001 36 1:4	EACH	2.000				
54262436	CONC ES 542006 36 1:4	EACH	4.000				
54262442	CONC ES 542006 42 1:4	EACH	12.000				
54264448	CONC ES 542016 48 1:4	EACH	6.000				
550A0050	STORM SEW CL A 1 12	FOOT	1,048.000				
550A0070	STORM SEW CL A 1 15	FOOT	454.000				
550A0090	STORM SEW CL A 1 18	FOOT	331.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0120	STORM SEW CL A 1 24	FOOT	547.000				
550A0140	STORM SEW CL A 1 30	FOOT	393.000				
550A0160	STORM SEW CL A 1 36	FOOT	386.000				
550A0180	STORM SEW CL A 1 42	FOOT	675.000				
550A0190	STORM SEW CL A 1 48	FOOT	434.000				
550A0340	STORM SEW CL A 2 12	FOOT	8,020.000				
550A0360	STORM SEW CL A 2 15	FOOT	953.000				
550A0380	STORM SEW CL A 2 18	FOOT	1,423.000				
550A0410	STORM SEW CL A 2 24	FOOT	1,978.000				
550A0430	STORM SEW CL A 2 30	FOOT	1,291.000				
550A0450	STORM SEW CL A 2 36	FOOT	639.000				
550A0470	STORM SEW CL A 2 42	FOOT	205.000				
550A0480	STORM SEW CL A 2 48	FOOT	1,216.000				
55100500	STORM SEWER REM 12	FOOT	175.000				
55100900	STORM SEWER REM 18	FOOT	410.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55101200	STORM SEWER REM 24	FOOT	25.000				
56100600	WATER MAIN 6	FOOT	46.000				
56100900	WATER MAIN 12	FOOT	4,617.000				
56104900	WATER VALVES 6	EACH	8.000				
56105200	WATER VALVES 12	EACH	20.000				
56200300	WATER SERV LINE 1	FOOT	82.000				
56400100	FIRE HYDNITS TO BE MVD	EACH	8.000				
56400300	FIRE HYDNITS TO BE ADJ	EACH	2.000				
56500400	DOM MET VLTS REM	EACH	1.000				
56500700	DOM WAT SER BOX REM	EACH	3.000				
56500800	DOM WAT SER BOX	EACH	3.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	590.000				
60100060	CONC HDWL FOR P DRAIN	EACH	47.000				
60100915	PIPE DRAINS 6	FOOT	1,000.000				
60100925	PIPE DRAINS 8	FOOT	1,000.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60100935	PIPE DRAINS 10	FOOT	1,000.000				
60100945	PIPE DRAINS 12	FOOT	1,000.000				
60100955	PIPE DRAINS 15	FOOT	1,000.000				
60100965	PIPE DRAINS 18	FOOT	1,000.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	2,127.000				
60218300	MAN TA 4 DIA T1F OL	EACH	6.000				
60218400	MAN TA 4 DIA T1F CL	EACH	31.000				
60218500	MAN TA 4 DIA T3F&G	EACH	20.000				
60219000	MAN TA 4 DIA T8G	EACH	3.000				
60219300	MAN TA 4 DIA T11F&G	EACH	2.000				
60221000	MAN TA 5 DIA T1F OL	EACH	1.000				
60221100	MAN TA 5 DIA T1F CL	EACH	11.000				
60221200	MAN TA 5 DIA T3F&G	EACH	3.000				
60222000	MAN TA 5 DIA T11F&G	EACH	1.000				
60223800	MAN TA 6 DIA T1F CL	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60224005	MAN TA 6 DIA T8G	EACH	1.000				
60224126	MH TYA 7 DIA, AFG 15	EA	2.000				
60224446	MAN TA 7 DIA T1F CL	EACH	15.000				
60224459	MAN TA 8 DIA T1F CL	EACH	5.000				
60234200	INLETS TA T1F OL	EACH	8.000				
60235700	INLETS TA T3F&G	EACH	145.000				
60235800	INLETS TA T4F&G	EACH	1.000				
60236200	INLETS TA T8G	EACH	40.000				
60236800	INLETS TA T11F&G	EACH	3.000				
60238305	INLET TA M INL 604101	EACH	6.000				
60240210	INLETS TB T1F OL	EACH	6.000				
60240215	INLETS TB T1F CL	EACH	2.000				
60240220	INLETS TB T3F&G	EACH	80.000				
60240301	INLETS TB T8G	EACH	12.000				
60240310	INLETS TB T11F&G	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60240366	INLET TB M INL 604106	EACH	1.000				
60265700	VV ADJUST	EACH	2.000				
60266100	VV RECONST	EACH	3.000				
60266600	VALVE BOX ADJ	EACH	4.000				
60406100	FR & LIDS T1 CL	EACH	1.000				
60603800	COMB CC&G TB6.12	FOOT	8,794.000				
60604400	COMB CC&G TB6.18	FOOT	65.000				
60605000	COMB CC&G TB6.24	FOOT	48,105.000				
60618300	CONC MEDIAN SURF 4	SQ FT	26,813.000				
61100605	MISC CONCRETE	CU YD	6.000				
61101007	STORM SEW PROT A 6	FOOT	1,000.000				
61101009	STORM SEW PROT A 8	FOOT	1,000.000				
61101011	STORM SEW PROT A 10	FOOT	1,000.000				
61101013	STORM SEW PROT A 12	FOOT	1,000.000				
61101017	STORM SEW PROT A 15	FOOT	1,000.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
61101020	STORM SEW PROT A 18	FOOT	1,000.000				
61133100	FLD TILE JUN VAULT 2D	EACH	20.000				
61133200	FLD TILE JUN VAULT 3D	EACH	20.000				
61139900	STORM SEWER SPEC 6	FOOT	1,500.000				
61140000	STORM SEWER SPEC 8	FOOT	1,500.000				
61140100	STORM SEWER SPEC 10	FOOT	1,500.000				
61140200	STORM SEWER SPEC 12	FOOT	1,500.000				
61140400	STORM SEWER SPEC 15	FOOT	1,500.000				
61140600	STORM SEWER SPEC 18	FOOT	1,500.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	475.000				
63100045	TRAF BAR TERM T2	EACH	1.000				
63100070	TRAF BAR TERM T5	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000				
63200310	GUARDRAIL REMOV	FOOT	1,345.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63500105	DELINEATORS	EACH	137.000				
64200116	SHOULDER RUM STRIP 16	FOOT	50,139.000				
66600105	FUR ERECT ROW MARKERS	EACH	127.000				
66700205	PERM SURV MKRS T1	EACH	19.000				
66900200	NON SPL WASTE DISPOSAL	CU YD	9,900.000				
66900400	SPL WAST GRD WAT DISP	GALLON	25,000.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	5.000				
66901000	BACKFILL PLUGS	CU YD	50.000				
67000400	ENGR FIELD OFFICE A	CAL MO	30.000				
67100100	MOBILIZATION	L SUM	1.000				
67201000	SEAL ABAN WATER WELLS	EACH	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	661.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	66.000				
70300100	SHORT TERM PAVT MKING	FOOT	490.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300210	TEMP PVT MK LTR & SYM	SQ FT	2,434.000				
70300220	TEMP PVT MK LINE 4	FOOT	370,087.000				
70300240	TEMP PVT MK LINE 6	FOOT	12,529.000				
70300250	TEMP PVT MK LINE 8	FOOT	15,189.000				
70300260	TEMP PVT MK LINE 12	FOOT	9,580.000				
70300280	TEMP PVT MK LINE 24	FOOT	922.000				
70300900	PAVT MARK TAPE T4 L&S	SQ FT	939.000				
70300904	PAVT MARK TAPE T4 4	FOOT	322,254.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	108,521.000				
70400100	TEMP CONC BARRIER	FOOT	1,913.000				
70400200	REL TEMP CONC BARRIER	FOOT	420.000				
70500100	TEMP SPBGR TY A	FOOT	25.000				
70500615	TEMP TR BAR TERM T1	EACH	2.000				
70500665	TEMP TR BAR TERM T6	EACH	2.000				
70600240	IMP ATTN TEMP NRD TL2	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70600340	IMP ATTN REL NRD TL2	EACH	2.000				
72000100	SIGN PANEL T1	SQ FT	933.000				
72000200	SIGN PANEL T2	SQ FT	84.000				
73000100	WOOD SIN SUPPORT	FOOT	2,346.000				
78003130	PREF PL PM TB LINE 6	FOOT	11,352.000				
78009000	MOD URETH PM LTR-SYM	SQ FT	1,918.000				
78009004	MOD URETH PM LINE 4	FOOT	133,564.000				
78009006	MOD URETH PM LINE 6	FOOT	1,177.000				
78009008	MOD URETH PM LINE 8	FOOT	15,189.000				
78009012	MOD URETH PM LINE 12	FOOT	7,603.000				
78009024	MOD URETH PM LINE 24	FOOT	505.000				
78100100	RAISED REFL PAVT MKR	EACH	1,362.000				
78100105	RAISED REF PVT MKR BR	EACH	16.000				
78100300	REPLACEMENT REFLECTOR	EACH	180.000				
78200100	MONODIR PRIS BAR REFL	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78200300	PRISMATIC CURB REFL	EACH	376.000				
78200410	GUARDRAIL MKR TYPE A	EACH	12.000				
78201000	TERMINAL MARKER - DA	EACH	6.000				
78300100	PAVT MARKING REMOVAL	SQ FT	799.000				
78300200	RAISED REF PVT MK REM	EACH	98.000				
80400100	ELECT SERV INSTALL	EACH	1.000				
80500010	SERV INSTALL GRND MT	EACH	2.000				
81028200	UNDRGRD C GALVS 2	FOOT	286.000				
81028220	UNDRGRD C GALVS 3	FOOT	44.000				
81028240	UNDRGRD C GALVS 4	FOOT	687.000				
81028320	UNDRGRD C PVC 1	FOOT	393.000				
81028350	UNDRGRD C PVC 2	FOOT	3,429.000				
81028360	UNDRGRD C PVC 2 1/2	FOOT	205.000				
81028370	UNDRGRD C PVC 3	FOOT	114.000				
81028390	UNDRGRD C PVC 4	FOOT	115.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81028750	UNDRGRD C CNC 2	FOOT	470.000				
81028770	UNDRGRD C CNC 3	FOOT	120.000				
81400700	HANDHOLE PCC	EACH	18.000				
81400720	DBL HANDHOLE PCC	EACH	2.000				
81603030	UD 2#4 #6G XLPUSE 1	FOOT	285.000				
81603040	UD 2#6 #8G XLPUSE 1	FOOT	7,770.000				
81702150	EC C XLP USE 1C 2	FOOT	200.000				
81702450	EC C XLP USE 3-1C 10	FOOT	5,205.000				
82102400	LUM SV HOR MT 400W	EACH	33.000				
82500340	LT CONT PEDM 480V 60	EACH	1.000				
83010500	LT P A 50MH 12MA	EACH	26.000				
83600300	LIGHT POLE FDN 30D	FOOT	182.000				
83800205	BKWY DEV TR B 15BC	EACH	26.000				
84200600	REM LT U NO SALV	EACH	2.000				
84200804	REM POLE FDN	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
84400105	RELOC EX LT UNIT	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	1.000				
85000500	MAIN EX FL BEACON INS	EACH	1.000				
86000100	MASTER CONTROLLER	EACH	1.000				
86200300	UNINTER POWER SUP EXT	EACH	2.000				
86400100	TRANSCEIVER - FIB OPT	EACH	2.000				
87100160	FO CAB C 62.5/125 24F	FOOT	2,891.000				
87300925	ELCBL C TRACER 14 1C	FOOT	2,891.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	1,363.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	2,671.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	4,113.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	3,031.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	7,246.000				
87301805	ELCBL C SERV 6 2C	FOOT	261.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	4,970.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87502440	TS POST GALVS 10	EACH	1.000				
87502500	TS POST GALVS 16	EACH	6.000				
87601100	PED P-B POST GALVS T1	EACH	3.000				
87702985	STL COMB MAA&P 52	EACH	2.000				
87702990	STL COMB MAA&P 54	EACH	1.000				
87703040	STL COMB MAA&P 62	EACH	1.000				
87703080	STL COMB MAA&P 68	EACH	2.000				
87703110	STL COMB MAA&P 74	EACH	1.000				
87800100	CONC FDN TY A	FOOT	27.000				
87800150	CONC FDN TY C	FOOT	6.000				
87800415	CONC FDN TY E 36D	FOOT	45.000				
87800420	CONC FDN TY E 42D	FOOT	96.000				
88000105	FLASH BEACON INSTALL	EACH	1.000				
88040070	SH P LED 1F 3S BM	EACH	5.000				
88040090	SH P LED 1F 3S MAM	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-  
 Code - 63 - 93 -  
 District - 3 - 3 -  
 Section Number - (110)R,BR & BR-1

Project Number  
 ACNCII-0326/088/

Route  
 FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88040110	SH P LED 1F 4S BM	EACH	1.000				
88040120	SH P LED 1F 4S MAM	EACH	3.000				
88040150	SH P LED 1F 5S BM	EACH	6.000				
88040160	SH P LED 1F 5S MAM	EACH	6.000				
88102825	PED SH P LED 1F BM CT	EACH	8.000				
88200410	TS BACKPLATE L F PLAS	EACH	33.000				
88500100	INDUCTIVE LOOP DETECT	EACH	24.000				
88600100	DET LOOP T1	FOOT	2,747.000				
88700200	LIGHT DETECTOR	EACH	7.000				
88700300	LIGHT DETECTOR AMP	EACH	2.000				
88800100	PED PUSH-BUTTON	EACH	8.000				
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89502375	REMOV EX TS EQUIP	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	8.000				
89502382	REMOV EX DBL HANDHOLE	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 66B83

State Job # - C-93-049-12

County Name - GRUNDY- KENDALL-

Code - 63 - 93 -

District - 3 - 3 -

Section Number - (110)R,BR & BR-1

Project Number

ACNCII-0326/088/

Route

FAP 326

\* REVISED: OCTOBER 28, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89502385	REMOV EX CONC FDN	EACH	5.000				
89502400	REM EX FB INSTAL COMP	EACH	1.000				

## FAA COORDINATION

Whenever any temporary construction operations or permanent improvements may affect navigable airspace, a Notice of Proposed Construction (Forms 7460-1 and 7460-2) must be filed with the FAA through their website. Determinations of No Hazard to Air Navigation must be received prior to construction. For this contract, the proximity of the Morris Municipal Airport requires filing 2 types of temporary construction activities for temporary obstruction evaluation plus filing for the permanent roadway improvement.

The contractor will have no responsibilities with regard to the permanent roadway improvement filings.

There are no fees associated with filing for evaluations or maintaining determinations.

Initial Determinations of No Hazard have been obtained by the Department to begin construction operations. Based on these determinations, marking and lighting are not necessary for aviation safety, however, lowering crane booms at night is required. The initial determinations for temporary operations are good for 12 month or 18 month periods after which time will need to be extended or resubmitted until the operations have been completed. The contractor is responsible for filing the extensions and obtaining determinations of no hazard. Operations that require determinations are...

- 1 Crane activity at the bridge sites. We assumed an 80' crane height for both bridge sites.
- 2 Dumping activity of tandem trucks. We assumed the highest point on the dump would not exceed 30'. The activity could be anywhere with the ROW from 1.61 miles southwest of the runway (station 6029+00) to 3.02 miles northwest of the runway (station 6309+00).

The Contractor shall comply with all FAA requirements and restrictions that result from FAA determinations. The Contractor is advised that he shall be responsible for all fines for non-compliance with FAA requirements.

The determinations all have an effective period. When the effective period ends it can be extended for one period. **THE CONTRACTOR IS RESPONSIBLE FOR ALL EXTENSION/RE-SUBMITTALS**. Extensions must be E-filed at least 15 days prior to the expiration date. Re-submittals must be E-filed at least 45 days prior to expiration. Extensions and re-submittals should be made through the FAA web site below:

<https://oeaaa.faa.gov/oeaaa/external/portal.jsp>

## TEMPORARY INFORMATION SIGN

(Effective May 15, 2013)

Description. This work shall consist of the furnishing, installation, maintenance, and removal of temporary information signs.

Materials. Materials shall be according to the applicable portions of Section 701 of the Standard Specifications and as shown on the plans.

Revised 10/25/13

Construction Requirements. The temporary information signs shall be in place at least one week prior to the beginning of construction activities that impact traffic flow and shall remain in place until the completion of the project. If all lanes are open for an extended period of time during the project, such as a winter shutdown, the Contractor shall cover the signs until lane closures resume.

Signs shall be installed according to the requirements of Section 701.

Basis of Payment. This work will be paid for at the contract unit price per Square Foot for TEMPORARY INFORMATION SIGN, in place.

**WEED CONTROL MOWING STRIP (SPECIAL)**

Description. This work consists furnishing labor, equipment, and materials to construct a Portland Cement Concrete weed control mowing strip as detailed in the plans.

It shall be constructed according to applicable portions of Section 606 and Article 606.10 except anchor walls will not be required.

The finished weed control mowing strip shall be flush with the final earth grades and consistent with the cross slopes as detailed in the plans.

Method of Measurement. This work will be measured for payment in place and the area computed in square yards (square meters). Earthwork for the construction of the mow strip will not be measured separately for payment.

Basis of Payment. This work will be paid for at the contract unit price per square yard (square meter) for WEED CONTROL MOWING STRIP (SPECIAL).

**BUILDING REMOVAL - CASE IV (NO ASBESTOS) (BDE)**

(Effective: September 1, 1990; Revised: April 1, 2010)

BUILDING REMOVAL: This work shall consist of the removal and disposal of two building(s), together with all foundations, retaining walls, and piers, down to a plane 1 ft (300 mm) below the ultimate or existing grade in the area and also all incidental and collateral work necessary to complete the removal of the building(s) in a manner approved by the Engineer. Any holes, such as basements, shall be filled with a suitable granular material. The building(s) are identified as follows:

<u>Bldg. No.</u>	<u>Parcel No.</u>	<u>Location</u>	<u>Description</u>
1	3VC0011	IL 47 Station 6058+20 78' LT	Wood frame & masonry 2 story, 2,100 sq. ft. shingle roof, wood siding
2	3VC0008	Granville Road Station 102+64 40' LT	Wood frame shed, metal roof, concrete slab floor, 750 sq. ft.

Revised 10/25/13