

PAVEMENT																				
LOCATION		GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE SUBGRADE IMPROVEMENT 12"	AGGREGATE SUBGRADE IMPROVEMENT 18"	SUBBASE GRANULAR MATERIAL, TYPE C	STABILIZED SUBBASE, 4"	BITUMINOUS MATERIALS (PRIME COAT) 0.375 LBS / SQ FT	BITUMINOUS MATERIALS (PRIME COAT) 0.10 LBS / SQ FT	LEVELING BINDER (MACHINE METHOD), N90	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	PCC PAVEMENT 10 1/2" (JOINTED)	PAVEMENT FABRIC	PROTECTIVE COAT	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	AGGREGATE SHOULDERS, TYPE B	PORTLAND CEMENT CONCRETE SHOULDERS 8"	WHITEWASHING FOR CONCRETE PAVEMENT	HOTMIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	
STATION	TO	STATION	SQ YD	SQ YD	SQ YD	TON	SQ YD	POUND	POUND	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD
URBAN GRUNDY																				
IL 47																				
6029+00.00	TO	6045+51.00	11593	7087	11593	1194	14919						13211	40	16220			3009	14919	
6045+51.00	TO	6061+51.08	4950	13154	4950	2972	14477						12637		15600			2963	14477	
6061+51.08	TO	6098+47.71	6321	33187	6321	4251	28432						25038		34137			9100	28432	
6098+47.71	TO	6117+59.58	6077	12929	6077	3546	12946						10693		15942	267	16	4982	12946	
6117+59.58	TO	6119+20.42	(BRIDGE OMISSION)																	
6119+20.42	TO	6151+62.25		34613		5267	24297						20980		29801	267	65	8554	24297	
6151+62.25	TO	6185+17.44	5750	28917	5750	5304	24043						20355		29453	267	16	8831	24043	
6185+17.44	TO	6186+70.56	(BRIDGE OMISSION)																	
6186+70.56	TO	6205+16.97		16649		1368	11997						10531		14016	267	526	3219	11997	
GRANVILLE RD.																				
100+52.00	TO	100+98.00		357			358						360		360				358	
PROLOGIS PRKWY.																				
1605+00.00	TO	1605+46.00		424			424						428		428				424	
NELSON RD.																				
208+12.00	TO	208+48.00		257			258						471		471				258	
AIRPORT RD.																				
308+59.00	TO	308+95.00		255			256						467		467				256	
MINOOKA RD.																				
408+09.00	TO	408+59.00		331			398						398		604			205	398	
409+39.00	TO	409+88.00		321			391						394		591			197	391	
URBAN GRUNDY SUB-TOTAL			34690	148480	34690	23901	133197						115963	40	158090	1067	623	41060	133197	
RURAL GRUNDY																				
IL 47																				
6205+16.97	TO	6257+48.41		49498		3894	37003						33630		48512		1459	14881	37003	
SHERRILL RD.																				
508+08.92	TO	508+50.99		334			406						405		606			202	406	
509+49.00	TO	509+90.80		333			403						403		606			203	403	
RURAL GRUNDY SUB-TOTAL				50165		3894	37812						34438		49724		1459	15285	37812	
RURAL KENDALL																				
IL 47																				
6257+48.41	TO	6277+00.00		12119		660	8802						7978		10445		228	2468	8802	
SOUTHBOUND CONNECTOR																				
10+00.00	TO	37+09.00		9074			24613	7569	87	3564	942						559		1469	
NORTHBOUND CONNECTOR																				
50+00.00	TO	65+52.00		2076			6429	1621		931	202						294			
RURAL KENDALL SUB-TOTAL				23269		660	8802	31041	9190	87	4495	1144	7978		10445		1082	2468	8802	1469
TOTAL			34690	221914	34690	28455	179811	40231		87	4495	1144	158379	40	218259	1067	3164	58813	179811	1469