

TEMPORARY PAVEMENT MARKING															
STATION	TO	STATION	SYMBOLS		LINES										
			ARROW & BIKE	TURN ARROW	4"		6"				8"		12"		24"
					SOLID WHITE	SOLID YELLOW	DOUBLE YELLOW	SKIP WHITE	SKIP YELLOW	SOLID WHITE	SOLID WHITE	DOTTED WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE
			SQ FT	EDGE OF PAV' T	EDGE OF PAV' T	CL & MEDIAN	CL	CL	X-WALK FOOT	LANE LINE	LINE	MED / DIAG	MED / DIAG	LINE	
URBAN GRUNDY															
IL 47															
6021+30.00	TO	6045+51.00	51.0	327.6	3603	2865	2670	994		387	2667	439	978	379	100
6045+51.00	TO	6061+51.00	30.6	140.4	3494	3044		744		265	2498	183	1291		97
6061+51.00	TO	6098+47.71	20.4	234.0	7263	7950		1791			1494	394	373	451	56
6098+47.71	TO	6151+62.25		187.2	10447	11079		2582			1449	238	641	428	
6151+62.25	TO	6205+16.97		140.4	10350	10806		2571			1131	194	516	236	
GRANVILLE RD.															
100+52.00	TO	107+21.00		46.8	1382		2179			137	180	27	132	151	27
PROLOGIS PRKWAY.															
1603+48.79	TO	1605+46.00		93.6	486		358				219				37
NELSON RD.															
200+48.75	TO	208+48.00		46.8	1687		1570				265	68			32
AIRPORT RD.															
300+00.00	TO	308+95.00		46.8	1879		1764				312	66			32
MINOOKA RD.															
403+58.00	TO	408+59.00		46.8	1069		954				264	46			31
409+39.00	TO	416+53.00		46.8	1491		1374				264	67			31
URBAN GRUNDY SUB-TOTAL			102.0	1357.2	43151	35744	10869	8682		789	10743	1722	3931	1645	443
RURAL GRUNDY															
IL 47															
6205+16.97	TO	6257+48.41		234.0	10252	11447		2571			1367	334	255	671	
SHERRILL RD.															
500+88.00	TO	508+59.00		46.8	1516		1494				265	67			31
509+39.00	TO	516+08.00		46.8	1399		1286				265	67			31
RURAL GRUNDY SUB-TOTAL				327.6	13167	11447	2780	2571			1897	468	255	671	62
RURAL KENDALL															
IL 47															
6257+48.41	TO	6277+00.00		130.8	2704	3153		199			284	75	122	147	
SOUTHBOUND CONNECTOR															
10+00.00	TO	37+09.00			3862	3581									832
NORTHBOUND CONNECTOR															
50+00.00	TO	65+52.00			1552	1554									
RURAL KENDALL SUB-TOTAL				130.8	8118	8288		199	288		284	75	122	979	
TOTAL				1918		133564			12529		15189		7603		505

SEALING ABANDONED WATER WELLS				
STATION	SIDE	PARCEL NO.	PREVIOUS OWNER	EACH
URBAN GRUNDY				
6152+62.26	LT	3VC0022	GRACE EVANGELICAL LUTHERAN CHURCH	1
TOTAL				1

PAVEMENT MARKING REMOVAL						
STATION	TO	STATION	TEMPORARY PAVEMENT MARKING			
			LINES			
			4"	6"	8"	12"
			SQ FT			
URBAN GRUNDY						
IL 47						
6021+30.00	TO	6029+00.00	284.3	60.0	297.3	96.9
TOTAL			798.6			
USE			799			

PERMANENT SURVEY MARKERS & LAND SECTION MARKERS				
LOCATION			PERMANENT SURVEY MARKERS, TYPE I	LAND SECTION MARKERS
STATION	OFFSET	DESCRIPTION	EACH	EACH
URBAN GRUNDY				
6045+49.84	1.22' RT	SECTION CORNER		1
6045+50.15	0'	P. I.	1	
6071+94.86	2.41' RT	QUARTER CORNER		1
6087+92.09	0'	P. I.	1	
6098+39.89	0.78' RT	SECTION CORNER		1
6103+72.09	0'	P. C.	1	
6106+58.81	0'	P. I.	1	
6109+45.29	0'	P. R. C.	1	
6112+32.49	0'	P. I.	1	
6115+19.45	0'	P. T.	1	
6125+03.68	40.82' RT	QUARTER CORNER		1
6131+64.31	0'	P. C.	1	
6133+48.75	0'	P. I.	1	
6135+33.12	0'	P. R. C.	1	
6137+17.56	0'	P. I.	1	
6139+01.94	0'	P. T.	1	
6151+63.49	24.31' RT	SECTION CORNER		1
6162+73.91	0'	P. C.	1	
6165+80.55	0'	P. I.	1	
6168+86.89	0'	P. R. C.	1	
6171+98.97	0'	P. I.	1	
6175+10.73	0'	P. T.	1	
6177+52.78	0'	P. I.	1	
6178+16.93	69.87' RT	QUARTER CORNER		1
6204+67.00	0'	P. O. T.	1	
6204+70.38	70.06' RT	SECTION CORNER		1
URBAN GRUNDY SUB-TOTAL			19	7
RURAL GRUNDY				
6231+19.19	92.08' RT	QUARTER CORNER		1
6125+03.68	40.82' RT	QUARTER CORNER		1
RURAL GRUNDY SUB-TOTAL				2
RURAL KENDALL				
6257+49.50	112.36' RT	SECTION CORNER		1
6257+50.46	165.19' RT	SECTION CORNER		1
RURAL KENDALL SUB-TOTAL				2
TOTAL			19	11

SHORT-TERM PAVEMENT MARKING			SHORT-TERM PAVEMENT MARKING			
STATION	TO	STATION	SKIP DASH	STATION	TO	STATION
			YELLOW CENTER LINE			
			FOOT			
			FOOT			
URBAN GRUNDY						
GRANVILLE RD.						
100+98.00	TO	107+21.00	62	500+88.00	TO	508+09.00
				509+91.00	TO	516+08.00
				RURAL GRUNDY SUB-TOTAL		
				134		
PROLOGIS PRKWAY.						
1603+48.79	TO	1605+46.00	20	TOTAL		
				490		
NELSON RD.						
200+48.75	TO	208+12.00	76			
AIRPORT RD.						
300+00.00	TO	308+59.00	86			
MINOOKA RD.						
403+58.00	TO	408+09.00	45			
409+88.00	TO	416+53.00	67			
URBAN GRUNDY SUB-TOTAL			356			