

SI = SPECIALTY ITEM

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	CITY 100%	CITY 100%	FED 80% STATE 20%	CITY 100%
				ROADWAY	ROADWAY	ROADWAY	BRIDGE	BRIDGE	HIGHWAY LIGHTING	TRAFFIC SIGNALS	TRAFFIC SIGNALS	CITY
				0003	0003	0003	0010	0010	0021	0021	0021	0043
				URBAN GRUNDY	RURAL GRUNDY	RURAL KENDALL	SN 032-0122	SN 032-0123	URBAN	PROLOGIS	GRANVILLE	URBAN
SI 81603040	UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	7770				GRUNDY	GRUNDY	7770			
SI 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	200						200			
SI 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	5205							2538	2667	
SI 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	33						26	3	4	
SI 82500340	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 480VOLT, 60AMP	EACH	1						1			
SI 83010500	LIGHT POLE, ALUMINUM, 50 FT. M. H., 12 FT. MAST ARM	EACH	26						26			
SI 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	182						182			
SI 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	26						26			
SI 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	2						2			
SI 84200804	REMOVAL OF POLE FOUNDATION	EACH	2						2			
SI 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1						1			
SI 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1							1		
SI 85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1							1		
SI 86000100	MASTER CONTROLLER	EACH	1								1	

14