

| CONCRETE SEALER | | | | | | | | | |
|-------------------|------------------|-------------------------------|-----------------------|------------|-----------------|----------------|-------------|-----------|---|
| STRUCTURE NUMBER | FACILITY CARRIED | APPROXIMATE LOCATION | FEATURE CROSSED | DECK WIDTH | PARAPET SURFACE | MEDIAN SURFACE | DECK LENGTH | SEAL AREA | TRAFFIC CONTROL AND PROTECTION STANDARD |
| | | | | FEET | FEET | FEET | FEET | SQ FT | |
| BUREAU INTERSTATE | | | | | | | | | |
| 006-0001 | I-80 EASTBOUND | 1.04 E/HENRY CO LN | KING CREEK | 40.2 | 7.4 | | 98.2 | 4,674 | 701406 |
| 006-0002 | I-80 WESTBOUND | 1.05 E/HENRY CO LN | KING CREEK | 40.2 | 7.4 | | 98.2 | 4,674 | 701406 |
| 006-0003 | I-80 EASTBOUND | 1.51 E/HENRY CO LN | BARBARA DITCH | 40.2 | 7.4 | | 73.5 | 3,499 | 701406 |
| 006-0004 | I-80 WESTBOUND | 1.52 E/HENRY CO LN | BARBARA DITCH | 40.2 | 7.4 | | 73.5 | 3,499 | 701406 |
| 006-0005 | I-80 EASTBOUND | 3.44 E/HENRY CO LN | ABBOTT DITCH | 40.2 | 7.4 | | 178 | 8,473 | 701406 |
| 006-0006 | I-80 WESTBOUND | 3.45 E/HENRY CO LN | ABBOTT DITCH | 40.2 | 7.4 | | 178 | 8,473 | 701406 |
| 006-0007 | I-80 EASTBOUND | 3.81 E/HENRY CO LN | COAL CREEK | 40 | 7.6 | | 176 | 8,378 | 701406 |
| 006-0008 | I-80 WESTBOUND | 3.82 E/HENRY CO LN | COAL CREEK | 40 | 7.6 | | 176 | 8,378 | 701406 |
| 006-0009 | I-80 EASTBOUND | 1.0 MI. W. OF IL 40 | DRAINAGE DITCH | 40.5 | 7.6 | | 136 | 6,542 | 701406 |
| 006-0010 | I-80 WESTBOUND | 1.0 MI. W. OF IL 40 | DRAINAGE DITCH | 40.5 | 7.6 | | 136 | 6,542 | 701406 |
| 006-0016 | I-80 WESTBOUND | 2 MI N WYANET | WEST BUREAU CREEK | 34 | 7.4 | | 43 | 1,780 | 701406 |
| 006-0017 | I-80 EASTBOUND | 2 MI N WYANET | WEST BUREAU CREEK | 34 | 7.4 | | 94.8 | 3,925 | 701406 |
| 006-0038 | I-180 NORTHBOUND | 4 MI E. OF PRINCETON | I-80 | 26.5 | 4.8 | | 273.2 | 8,551 | 701456 * |
| 006-0039 | I-180 SOUTHBOUND | 4 MI E. OF PRINCETON | I-80 | 26.5 | 4.8 | | 272.2 | 8,520 | 701456 * |
| 006-0041 | I-180 SOUTHBOUND | 3.4 MI S JCT FAI 80 | EAST BUREAU CREEK | 39 | 5 | | 150.1 | 6,604 | 701406 * |
| 006-0042 | I-180 NORTHBOUND | 3.4 MI S JCT FAI 80 | EAST BUREAU CREEK | 39 | 5 | | 147.5 | 6,490 | 701406 * |
| 006-0043 | I-180 NORTHBOUND | 1.1 MI N ILL 26 | BRUSH CREEK | 39 | 5 | | 191 | 8,404 | 701406 * |
| 006-0044 | I-180 SOUTHBOUND | 1.1 MI N ILL 26 | BRUSH CREEK | 39 | 5 | | 191 | 8,404 | 701406 * |
| 006-0045 | I-180 SOUTHBOUND | 2 MI NW BUREAU JCT | ILL 26 | 39 | 5 | | 212.5 | 9,350 | 701406, 701411 * |
| 006-0046 | I-180 NORTHBOUND | 2 MI NW BUREAU JCT | ILL 26 | 39 | 5 | | 212.5 | 9,350 | 701406, 701411 * |
| 006-0047 | I-180 SOUTHBOUND | 0.5 MI S JCT ILL 26 | EAST BUREAU CREEK | 39 | 5 | | 211.1 | 9,288 | 701406, 701411 SB * |
| 006-0048 | I-180 NORTHBOUND | 0.5 MI S JCT ILL 26 | EAST BUREAU CREEK | 39 | 5 | | 211.1 | 9,288 | 701406 * |
| 006-0049 | I-180 SOUTHBOUND | 0.7 MI S ILL 26 | IAIS RR ,I & M CANAL | 39 | 5 | | 716.8 | 31,539 | 701406 * |
| 006-0050 | I-180 NORTHBOUND | 0.7 MI S ILL 26 | IAIS RR, I & M CANAL | 39 | 5 | | 716.8 | 31,539 | 701406 * |
| 006-0051 | I-180 SOUTHBOUND | 1.2 M S JCT ILL 26 | BUREAU CREEK | 39 | 5 | | 371.5 | 16,346 | 701406 * |
| 006-0052 | I-180 NORTHBOUND | 1.2 MI S JCT ILL 26 | BUREAU CREEK | 39 | 5 | | 371.5 | 16,346 | 701406 * |
| 006-0053 | I-180 SOUTHBOUND | 1.4 MI S JCT ILL 26 | BOTTOM RD FAS 246 | 39 | 5 | | 176.3 | 7,757 | 701406 * |
| 006-0054 | I-180 NORTHBOUND | 1.4 MI S JCT ILL 26 | BOTTOM RD FAS 246 | 39 | 5 | | 176.3 | 7,757 | 701406 * |
| 006-0055 | I-180 EASTBOUND | 3 MI W HENNEPIN | FAP 318 NB | 39 | 5 | | 328.4 | 14,450 | 701406 * |
| 006-0056 | I-180 EASTBOUND | 3 MI W HENNEPIN | I-180 RMP 10.01 | 39 | 5 | | 234 | 10,296 | 701406 * |
| 006-0057 | I-180 EASTBOUND | 2 MI SW BUREAU JCT. | IL 29(SBI29A)&IAIS RR | 63 | 5 | | 393 | 26,724 | 701406, 701411 * |
| 006-0058 | I-180 WESTBOUND | 2 MI. SW BUREAU JCT. | IL 29(SBI29A)&IAIS RR | 69.7 | 5 | | 383.8 | 28,670 | 701406, 701411 * |
| 006-0059 | I-180 WESTBOUND | 1.5 MI W HENNEPIN | ILL 26 & BUREAU CRK. | 39 | 5 | | 401 | 17,644 | 701406, 701411 * |
| 006-0060 | I-180 EASTBOUND | 1.5 MI W HENNEPIN | ILL 26 & BUREAU CRK. | 39 | 5 | | 401 | 17,644 | 701406 * |
| 006-0151 | I-80 EASTBOUND | 2 MI. W. OF IL 26 | BUREAU CREEK | 40 | 7.4 | | 292 | 13,841 | 701406 |
| 006-0152 | I-80 WESTBOUND | 2 MI. W. OF IL 26 | BUREAU CREEK | 40 | 7.4 | | 292 | 13,841 | 701406 |
| 006-0165 | I-80 EASTBOUND | 1.7 MI E JCT ILL 89 | SPRING CREEK | 40 | 7.6 | | 170 | 8,092 | 701406 |
| 006-0166 | I-80 WESTBOUND | 1.7 MI E JCT ILL 89 | SPRING CREEK | 40 | 7.6 | | 170 | 8,092 | 701406 |
| 006-0167 | I-80 EASTBOUND | 1.9 MI E JCT ILL 89 | BN RR | 40 | 7.6 | | 154.5 | 7,354 | 701406 |
| 006-0168 | I-80 WESTBOUND | 1.9 MI E JCT ILL 89 | BN RR | 40 | 7.6 | | 154.5 | 7,354 | 701406 |
| 006-0170 | I-80 EASTBOUND | 4.6 MI E JCT FAI 180--MP 65.6 | CREEK & TR 352 | 40 | 7.6 | | 310.1 | 14,761 | 701406 |
| 006-0171 | I-80 WESTBOUND | 4.6 MI E JCT FAI 180--MP 65.6 | CREEK & TR 352 | 40 | 7.6 | | 356.9 | 16,988 | 701406 |
| 006-0172 | I-80 EASTBOUND | 1.2 MI E JCT FAI 180--MP 62.2 | E. BUREAU CREEK | 40.3 | 7.6 | | 172.1 | 8,244 | 701406 |
| 006-0173 | I-80 WESTBOUND | 1.2 MI E JCT FAI 180--MP 62.2 | E. BUREAU CREEK | 40.3 | 7.6 | | 172.1 | 8,244 | 701406 |
| 006-0174 | I-80 EASTBOUND | 1.8 MI W ILL 89--MP 68.3 | NEGRO CREEK | 40.8 | 7.6 | | 221 | 10,696 | 701406 |
| 006-0175 | I-80 WESTBOUND | 1.8 MI W ILL 89--MP 68.3 | NEGRO CREEK | 40.8 | 7.6 | | 221 | 10,696 | 701406 |

* STRUCTURE HAS EXISTING PCC OVERLAY, ADDITIONAL DRYING TIME BY BE REQUIRED

| | | | | | | | | | | | | | | |
|--|----------------------|------------|-----------|---|-------------------------|-----------|----|--------|-----------|---------|--------|--------------------|------------------|---|
| FILE NAME = | USER NAME = duncanbd | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SEALING SCHEDULE | | | | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| et:\pw\work\p1dot\duncanbd\0324748\03670-shit-schedule.dgn | | DRAWN - | REVISED - | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. | VAR | ILLINOIS | FED. AID PROJECT | |
| | | CHECKED - | REVISED - | | | | | | | | | VARIOUS | 11 | 4 |
| | | DATE - | REVISED - | | | | | | | | | CONTRACT NO. 66C70 | | |