

CONCRETE SEALER									
STRUCTURE NUMBER	FACILITY CARRIED	APPROXIMATE LOCATION	FEATURE CROSSED	DECK WIDTH	PARAPET SURFACE	MEDIAN SURFACE	DECK LENGTH	SEAL AREA	TRAFFIC CONTROL AND PROTECTION STANDARD
				FEET	FEET	FEET	FEET	SQ FT	
BUREAU									
NON-INTERSTATE									
006-0083	ILL ROUTE 29 AND 26	0.3 MI N JCT ILL 26	BUREAU CR OVERFLOW	34	7.4		308	12,751	701201
006-0084	ILL ROUTE 29	0.1 MI S JCT ILL 26	BUREAU CREEK	35.9	7.4		218	9,439	701201
006-0085	FAP 318 NB	3 MI W OF HENNEPIN	I-180 EX RMP 1001	39	5		372.7	16,399	701406 *
006-0086	ILL 40	3.1 MI S JCT ILL 92	WALNUT SPECIAL DITCH	40	7.4		42.8	2,029	701201
006-0090	ILL 40	0.4 MI S JCT I-80	I&M CANAL	32	7.4		173.8	6,848	701201
006-0096	ILL 92	1.0 MI E ILL 172	I&M FEEDER CANAL	30	1.7		89.5	2,837	701201
006-0097	ILL 92	1.4 MI W JCT ILL 40	GREEN RIVER	32	7.4		170	6,698	701201
006-0101	IL 92	.7 MI W VAN ORIN	BR MASTERS CR	32	7.4		60.3	2,376	701201
006-0112	FAS 188	2 MI N US6 @ WYANET	I-80	26	1.83		216.7	6,031	701201
006-0114	TISKILWA SPUR	0.3 MI N TISKILWA	BUREAU CREEK	32	7.4		379	14,933	701201
006-0116	FAS 244/BACKBONE RD	1.8 MI W JCT ILL 26	I-80	28	7.6		208.5	7,423	701201
006-0123	TR 148	3.0 MI. E. OF IL 40	I-80	24	1.83		216.7	5,597	701201
006-0124	TR 188	4.3 MI W JCT ILL 26	I-80	24	1.83		235	6,070	701201
006-0125	TR 241	0.9 MI S JCT FAI 80	I-180	30.5	5		277.6	9,855	701201
006-0126	TR 281	1.4 MI N ILL 26	I-180	28.5	5		314	10,519	701201
006-0127	TR 322(2600E)	1.6 MI E JCT I-180	I-80	24	1.83		217.5	5,618	701201
006-0128	TR 333	2.5 MI N JCT ILL 29	I-180	26.5	5		282.9	8,911	701201
006-0129	TR 364 (3000E)	1.4 MI N SEATONVILLE	I-80	24	1.83		250	6,458	701201
006-0133	TR 370 (3100E)	2.2 MI W ILL 89	I-80	24	1.83		268.3	6,930	701201
006-0135	US RT 34	1.1MI NE JCT ILL 26	BN RR	42.5	5		348.8	16,568	701201 *
006-0137	US 6	1.3 MI E OF I-180	E BUREAU CREEK	30	7.4		156	5,834	701201
006-0138	ILL 40	SOUTH EDGE OF BUDA	BN RR	42.5	5		349	16,578	701501
006-0142	ILL 89	0.8 MI S ARLINGTON	BRANCH OF BRUSH CR.	32	1.8		63.5	2,146	701201
006-0143	ILL 29	NORTHEAST EDGE DEPUE	NEGRO CREEK	32	7.4		153.3	6,040	701201
006-0144	US RT 6	IN SEATONVILLE	NEGRO CREEK	32	7.4		105.3	4,149	701201
006-0145	ILL 40	1.2 MI S OF BUDA	COAL CREEK	32	7.4		118	4,649	701201
006-0148	IL 26 & IL 29	S EDGE BUREAU JCT.	HENNEPIN CANAL	32	7.4		168	6,619	701501
006-0149	ILL 92	1.6 MI. W. US 34	BUREAU CREEK	32	7.4		306	12,056	701201
006-0153	IL 92	3.3 MI. W. OF US 34	STREAM	32	7.4		82.1	3,235	701201
006-0154	US 6/34	1 MI. W OF PRINCETON	BIG BUREAU CREEK	40	7.4		235.2	11,148	701201
006-0155	IL 29	EAST EDGE OF DEPUE	DRAINAGE DITCH	32	7.4		116	4,570	701201
006-0156	IL 40	3.5 MI. N. OF I-80	HICKORY CREEK	40	7.4		74.1	3,512	701201
006-0157	IL 40	3 MI. N. OF I-80	DITCH # 4	40	7.4		65	3,081	701201
006-0158	US 6	E EDGE SPRING VALLEY	SPRING CR & ABANDN RR	72	7.4		205	16,277	701606
006-0159	IL 26	0.3 MI. NW OF I-180	E. BUREAU CREEK	44	7.6	14.2	317.4	20,885	701201
006-0160	IL 92	1 MI. E. OF WALNUT	UNNAMED STREAM	32	7.4		78.5	3,093	701201
006-0161	US 6 & 34	AT EAST EDGE WYANET	WEST BUREAU CREEK	36	7.4		150	6,510	701201
006-0162	IL 26	N. EDGE OF PRINCETON	I-80	66.5	7.6	9	216.5	17,991	701601
006-0163	NEW BEDFORD RD	0.6 MI W JCT IL 40	GREEN RIVER	28	7.6		165	5,874	701201
006-0164	IL 89	0.60 MI S OF US 6	RI RAILROAD	30	4.6		230	7,958	701501
006-0169	US RT 6	W OF DEPUE SPUR	BRUSH CREEK	32	7.6		127	5,029	701201
006-0178	ILL 89	S. EDGE OF LADD	I-80	56	7.6	7	214.6	15,151	701606
006-0181	IL 89	0.5 MI S JCT US 34	PIKE CREEK	32	7.6		145	5,742	701201
006-0182	US 34	0.5 MI SW LAMOILLE	PIKE CREEK	32	7.6		105	4,158	701201
BUREAU COUNTY SUB-TOTAL								864,576	
DEKALB COUNTY									
NON-INTERSTATE									
019-0005	ILL 23	0.7 MI S JCT ILL 72	CC & PAC. RR	48			142.8	6,854	701201 *
019-0012	ILL 64	1.5 MI W JCT ILL 23	S BR KISHWAUKEE RIV.	34	7.4		121.5	5,030	701201
019-0021	ILL 72	0.1 MI E OGLE CO	STREAM	32	3		40.2	1,407	701201
019-0026	ILL 72	W EDGE GENOA	S BR KISHWAUKEE RIV.	36	7.4		230	9,982	701201
019-0030	ILL 72	1.3 MI W OF KIRKLAND	OWENS CREEK	32	7.4		164	6,462	701201
019-0032	US 30	.5 MI E OF SHABBONA	BN RR	32	7.4		299.8	11,812	701201
019-0033	ILL 72	.5 MI W KANE CO LN	COON CREEK	34	7.4		82	3,395	701201
019-0034	ILL 72	1.5 MI W KINGSTON	LEE SLOUGH	32	7.4		73.5	2,896	701201
019-0035	ILL 23	1 MI N JCT ILL 72	DEER CREEK TRIB.	32.7			39.7	1,298	701201
019-0036	US 30	.5 MI W HINCKLEY	LITTLE ROCK CREEK	40	7.4		137	6,494	701201
019-0037	ILL 72	3 MI NW OF KIRKLAND	DRAINAGE DITCH	32	7.4		55	2,167	701201
019-0038	IL 72	0.3 MI. W. KIRKLAND	UNNAMED CREEK	32	7.4		40.7	1,604	701201
019-0039	US 34	1.1 MI. W. SANDWICH	SOMONAUK CREEK	40	7.4		126.5	5,996	701201
019-0040	IL 64	5 MI. E. OGLE CO LN	OWENS CREEK	36	7.4		69	2,995	701201
019-0041	IL 38	1.5 MI. E. CRESTON	E. BR. KILBUCK CREEK	40	7.4		75	3,555	701201
019-0043	ILL 23	0.4 MI N JCT ILL 64	E BR,S BR KISHW* RIV	59	7.4		120.6	8,008	701501
019-0044	IL 38	0.6 MI W JCT IL 23	S BR KISHWAUKEE RIV.	59	1.6		118	7,151	701602
019-0045	IL 38	1.9 MI E SOMONAUK RD	UNION DITCH #1	40	7.6		61.5	2,927	701201
019-0047	ILL 72	W EDGE OF KIRKLAND	S00 LINE/IC & E RR	32	7.6		163.5	6,475	701201
DEKALB COUNTY SUB-TOTAL								96,507	

\* STRUCTURE HAS EXISTING PCC OVERLAY, ADDITIONAL DRYING TIME BY BE REQUIRED

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SEALING SCHEDULE</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p1dot\duncanbd\0324748\03670-shit-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	VARIOUS	11	5
		CHECKED -	REVISED -		*D3 BRIDGE DECK SEALING 2014								CONTRACT NO. 66C70
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								