

80/20

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				0004	0011
				ROADWAY	STRUCTURAL
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	272	272	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	106	106	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	58	58	
44000100	PAVEMENT REMOVAL	SO YD	161	161	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	2,827	2,827	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	133	133	
44004250	PAVED SHOULDER REMOVAL	SO YD	847	847	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	262	262	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	222	222	
50200100	STRUCTURE EXCAVATION	CU YD	809		809
50200300	COFFERDAM EXCAVATION	CU YD	77		77
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1		1
50300100	FLOOR DRAINS	EACH	24		24

NOTES:
 • SPECIALTY ITEM