

QUANTITIES FOR	CONCRETE PIPES
INSIDE DIAMETER	ESTIMATED
OF PIPE	CLASS SI CONCRETE
OI IIIL	
	REQUIRED
	20" (500 mm) WIDTH
INCH (mm)	CU.YD. (m3)
4" (100)	0.14 (0.11)
6" (150)	0.16 (0.12)
8" (200)	0.19 (0.14)
10" (250)	0.22 (0.17)
12" (300)	0.25 (0.19)
15" (375)	0.30 (0.23)
18" (450)	0.35 (0.27)
24'' (600)	0.45 (0.35)
30'' (750)	0.57 (0.43)
36" (900)	0.69 (0.53)
42" (1050)	0.83 (0.63)
48" (1200)	0.97 (0.74)
54'' (1350)	1.12 (0.86)
60'' (1500)	1.28 (0.98)

QUANTITIES FO	OR METAL PIPES						
INSIDE DIAMETER	ESTIMATED						
OF PIPE	CLASS SI CONCRETE						
	REQUIRED						
	20" (500 mm) WIDTH						
INCH (mm)	CU. YD. (m3)						
4" (100)	0.12 (0.09)						
6" (150)	0.14 (0.11)						
8" (200)	0.16 (0.12)						
10" (250)	0.19 (0.14)						
12" (300)	0.21 (0.16)						
15" (375)	0.25 (0.19)						
18" (450)	0.29 (0.22)						
24" (600)	0.38 (0.29)						
30" (750)	0.47 (0.36)						
36" (900)	0.59 (0.45)						
42" (1050)	0.69 (0.53)						
48" (1200)	0.81 (0.62)						
54'' (1350)	0.93 (0.71)						
60'' (1500)	1.05 (0.81)						

GENERAL NOTES

- 1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
- 2. WHEN CONCRETE COLLARS ARE USED TO CONNECT PIPES OF DIFFERENT OUTSIDE DIAMETERS, THE CONCRETE COLLAR SHALL BE FORMED USING THE LARGEST OUTSIDE DIAMETER (SEE END VIEW).
- 3. THE WIRE MESH SHALL WEIGH NOT LESS THAN 54#/100 SQ. FT. (2.63 kg/m²).
- 4. WHEN CONCRETE COLLARS ARE CONSTRUCTED ADJACENT TO AN EXISTING CONCRETE STRUCTURE (HEADWALLS, ETC.) EXPANSION BOLTS, SHALL BE USED AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, EACH, FOR EXPANSION BOLTS OF THE SIZE SPECIFIED IN THE PLANS.
- 5. CONCRETE COLLARS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, PER CUBIC YARD (CUBIC METER), FOR CONCRETE COLLARS INCLUDING ALL MATERIAL AND LABOR SPECIFIED TO COMPLETE THE WORK IN PLACE.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

DISTRICT 5 DETAIL NO. 54248510

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	57-20(HB,HB-1)BR-1	MCLEAN	440	288
		CONTRACT	NO. 7	0570

FILE NAME =	USER NAME = detersbj	DESIGNED -	REVISED - 12/06
c:\pw_work\pwidot\detersbj\d0157116\D570	570-sht-details.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 8/13/2013	DATE -	REVISED -

STATE OF ILLINOIS							
DEPARTMENT	0F	TRANSPORTATION					

SCALE:

CONCRETE COLLAR						F.A.P RTE.		SECTION					co	
						704		57-	20(HB	HB-1)BR	-1		МС	
														CO
	SHEET	٧٥.	OF	SHEETS	STA.	TO STA.	EED	POAD	nter	NΛ	TI I TMOTS	EED	AID	PPA