

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP		
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP		
				0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN		
*M2500600	POTASSIUM FERTILIZER NUTRENT	KG	370	370								
M2020010	EARTH EXCAVATION	CU M	6445	6445								
M2080150	TRENCH BACKFILL	CU M	4730	4730								
*M2500100	SEEDING, CLASS 1	HA	2.4	2.4								
*M2500200	SEEDING, CLASS 2	HA	2.5	2.5								
*M2500700	AGRICULTURAL GROUND LIMESTONE	M TON	16.6	16.6								
M2510115	MULCH, METHOD 2	HA	2.5	2.5								
M2510125	MULCH, METHOD 3	HA	2.3	2.3								
M2510635	HEAVY DUTY EROSION CONTROL BLANKET	SO M	592	592								
M2820200	FILTER FABRIC	SO M	25	25								
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	1644	1644								
M2800305	TEMPORARY DITCH CHECKS	METER	29	29								
M2810105	STONE RIPRAP, CLASS A3	SO M	25	25								
M3110200	SUB-BASE GRANULAR MATERIAL, TYPE A 200MM	SO M	14482	14482								
M3510150	AGGREGATE BASE COURSE, TYPE A 150MM	SO M	730	730								
M3510200	AGGREGATE BASE COURSE, TYPE A 200MM	SO M	404	404								

110

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE: NONE
DATE: 06/2013

DRAWN BY: CE
CHECKED BY: FML