

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	12

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP		
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP		
				0003 URBAN	0021 URBAN				0028 URBAN			
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SO M	1665	1665								
M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100 MM	SO M	4558.0		2876.0	1682.0						
M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150 MM	SO M	344.0	344								
M4240200	PORTLAND CEMENT CONCRETE SIDEWALK 200 MM	SO M	651.5	651.5								
M4248000	DETECTABLE WARNINGS	SO M	29.0	29								
M4402000	PAVEMENT REMOVAL	SO M	8841	8841								
M4402010	DRIVEWAY PAVEMENT REMOVAL	SO M	1386	1386								
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	257	257								
M4402050	SIDEWALK REMOVAL	SO M	69	69								
M4402530	PAVED SHOULDER REMOVAL	SO M	4453	4453								
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SO M	38	38								
M4423300	PAVEMENT PATCHING, TYPE III 300MM	SO M	39	39								
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	3626	3626								
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	59	59								

14

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)  
SECTION 28R-1  
SANGAMON COUNTY

SCALE: NONE  
DATE: 06/2013

DRAWN BY: GE  
CHECKED BY: FML