


F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1597	14 (W, RS-7)	ADAMS/PIKE	152	25
FED. ROAD DIST. NO. 6		ILLINOIS	FED. AID PROJECT	



TYPICAL FAS 1597 (IL 96) SECTION

STA 984+40.00 TO STA 985+00.00
 STA 984+40.00 TO STA 1324+00.00
 STA 1325+12.00 TO STA 1338+64.00
 STA 1350+48.00 TO STA 1351+73.00
 STA 1378+57.00 TO STA 1399+59.00
 STA 1410+22.00 TO STA 1436+65.00
 STA 1435+00.00 TO STA 1436+65.00

STATION EQUATIONS

STA 986+00.00 BK = 1320+76.11 AH
 STA 984+40.00 TO STA 985+00.00 ** (E8)
 STA 1435+00.00 TO STA 1436+65.00 ** (E8)


*NOTE:
 SEE PLAN AND PROFILE SHEETS FOR THE LOCATIONS OF THE AGGREGATE AND HOT-MIX ASPHALT SHOULDERS

LEGEND

- (E1) EX 9" - 6" - 9" PCC PAVEMENT
- (E2) EX HOT-MIX ASPHALT BINDER AND SURFACE COURSE, VARIABLE DEPTH (4 1/2" TYP., 3" MIN.)
- (E3) EX HOT-MIX ASPHALT BINDER AND SURFACE COURSE, 3"
- (E4) EX HOT-MIX ASPHALT BINDER AND SURFACE COURSE, VARIABLE DEPTH (2 1/2" MIN.)
- (E5) EX HOT-MIX ASPHALT BASE COURSE WIDENING, 12"
- (E6) EX HOT-MIX ASPHALT SHOULDERS, 6"
- (E7) EX HOT-MIX ASPHALT SHOULDERS, VARIABLE DEPTH
- (E8) EX HOT-MIX ASPHALT BASE COURSE WIDENING, 9"
- (E9) EX AGGREGATE SHOULDER

- (1) PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, 1 1/2"
- (2) PROPOSED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, VARIABLE DEPTH
- (3) PROPOSED LEVELING BINDER (MACHINE METHOD), N50, 1 1/4"
- (4A) PROPOSED HOT-MIX ASPHALT BASE COURSE WIDENING, 10"
- (4B) PROPOSED HOT-MIX ASPHALT BASE COURSE, 10"
- (5) PROPOSED AGGREGATE SHOULDER, TYPE B
- (6) PROPOSED HOT-MIX ASPHALT SHOULDER, 2 1/2"
- (6A) PROPOSED HOT-MIX ASPHALT SHOULDER, 8"
- (7) PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (3/4" AVG.)
- (8) PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (2 1/2" AVG.)
- (9) PROPOSED PAVEMENT MARKING LINE, 5"
- (10) PROPOSED CONCRETE GUTTER, TYPE A
- (11) PROPOSED PIPE UNDERDRAINS, 4"
- (12) NOT USED
- (13) NOT USED
- (13A) NOT USED
- (14) PROPOSED HOT-MIX ASPHALT BASE COURSE, 6 1/2"
- (15) PROPOSED STRIP REFLECTIVE CRACK CONTROL TREATMENT
- (16) PROPOSED INCIDENTAL HOT-MIX ASPHALT SURFACING - 1 1/2"

- (A) SHOULDER SLOPE HIGH SIDE OF SE:
 SHOULDER SHALL BE SLOPED AT 1/2" / FT (4%) IF THE SE IS BETWEEN 0% AND 4%. IF SE IS GREATER THAN 4% THE SHOULDER SHALL BE SLOPED SO THE ALGEBRAIC DIFFERENCE BETWEEN THE PAVEMENT CROSS SLOPE AND THE SHOULDER SLOPE DOES NOT EXCEED 8%. WHEN THE SE IS 8%, THE SHOULDER SLOPE SHALL BE 1% TOWARD THE LANES OF TRAFFIC TO FACILITATE DRAINAGE.
- (B) SHOULDER SLOPE LOW SIDE OF SE:
 SLOPE SHALL BE THE SAME AS THE SE BUT NOT LESS THAN 4.0%.




TYPICAL FAS 1597 (IL 96) SECTION

STA 1324+00.00 TO STA 1325+70.00
 STA 1329+10.00 TO STA 1325+12.00


STATION EQUATIONS

STA 1329+72.29 BK = 1324+34.67 AH



TYPICAL FAS 1597 (IL 96) SECTION

STA 1325+70.00 TO STA 1326+86.10
 STA 1326+86.10 TO STA 1327+98.90 - BRIDGE OMISSION
 STA 1327+98.90 TO STA 1329+10.00



AGGREGATE SHOULDER, TYPE B DETAIL

NOT TO SCALE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS
 SHEET 1 OF 4

F.A.S. ROUTE 1597 (IL 96)
 SECTION 14 (W, RS-7)
 ADAMS/PIKE COUNTY

SCALE: NTS
 DATE

DRAWN BY BNK
 CHECKED BY DBS