

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N.084-0150	S.N.084-0151	S.N.084-0154
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	11460.1	11460.1			
60622400	CONCRETE MEDIAN, TYPE SM-6.00	SQ FT	3496.1	3496.1			
X16D161702	CONCRETE MEDIAN, TYPE SM (DOWELLED)	SQ FT	3496.1	3496.1			
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	8	8			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	525	525			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6			
63200310	GUARDRAIL REMOVAL	FOOT	1238	1238			
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	175	175			
* 63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	2			
* 63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	2	2			
63500105	DELINEATORS	EACH	226	226			
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	110303	110303			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			

△

14

*SPECIALTY ITEM

FILE NAME =	USER NAME = sparksg	DESIGNED -	REVISED - 10/28/13	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES COMBINED- PARTS "A" & "B"			F.A.I. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pwork\sparksg\100221183\067298-shl-SD0.dgn	PLOT SCALE = 1/8"=1'-0"	DRAWN -	REVISED -					1-72	*	SANGAMON	194	9
Default	PLOT DATE = Sep-06-2013 10:45:22AM	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 72C90	
		DATE -	REVISED -									