

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				90% FED ROADWAY	10% STATE NONE
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	652	652	
X4000115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	Pounds	125,172	125,172	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2813	2813	
40600990	TEMPORARY RAMP	SQ YD	1529	1529	
40803240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	39723	39723	
40803345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	14926	14926	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	77678	77678	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	22415	22415	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2293	2293	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	96970	96970	
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SQ YD	80387	80387	
44004250	PAVED SHOULDER REMOVAL	SQ YD	100	100	
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	30	30	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				90% FED ROADWAY	10% STATE NONE
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	60	60	
44200929	CLASS B PATCHES, TYPE I, 8 INCH	SQ YD	20	20	
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	40	40	
44201299	DOWEL BARS 1 1/2"	EACH	170	170	
4421300	PATCHING REINFORCEMENT	SQ YD	90	90	
44213100	PAVEMENT FABRIC	SQ YD	150	150	
44213200	SAW CUTS	FOOT	1400	1400	
44213204	TIE BARS 3/4"	EACH	6	6	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	11288	11288	
48203042	HOT-MIX ASPHALT SHOULDERS, 11 1/4"	SQ YD	60	60	
48203047	HOT-MIX ASPHALT SHOULDERS, 12 1/2"	SQ YD	40	40	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	15073	15073	
63500105	DELINEATORS	EACH	226	226	
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	110303	110303	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	



Rev.

* ITEM REQUIRES SPECIAL PROVISION

USER NAME : sparksgw	DESIGNED - BTM	REVISED - 10/26/13	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 2.0000' / 1"	DRAWN - BTM	REVISED -						I-72	*	SANGAMON	194	16
PLOT DATE : Sep-05-2013 07:43:11AM	CHECKED - JSA	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				* (84-10-1)RS-3, (84-10-2)RS-4 CONTRACT NO. 72C90				
	DATE - 12/19/12	REVISED -						ILLINOIS FED. AID PROJECT				