



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 30, 2013

SUBJECT: FAI Route 72 (I-72)  
Project ACNHPP-0072(401)  
Section (84-10-1RS-3, 84-10-2RS-4)BR, I  
Sangamon County  
Contract No. 72C90  
Item No. 40, November 8, 2013 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 4, 15, 16, and 62 of the Plans.
3. Revised page 4 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger, P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Roger Driskell, Region 4, District 6; Tim Kell; D. Carl Puzey; Estimates

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

County Name - SANGAMON - -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0320157	CLEAN UNDERDR OUTLET	EACH	330.000				
X2503000	MAINTENANCE MOWING	ACRE	156.000				
X4060115	P BIT MATLS PR CT	POUND	141,868.000				
X4403800	MEDIAN SURF REMOVAL	SQ FT	16,799.800				
X6050700	REMOVE INLET BOX	EACH	8.000				
*ADD X6061702	CONC MED TSM DOW	SQ FT	3,496.100				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
*ADD X7200201	WIDTH RESTRICT SIGN	L SUM	1.000				
X7830072	GRV RCSD PVT MRKG 6	FOOT	139,241.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	354.000				
Z0001900	ASB BEARING PAD REMOV	EACH	54.000				
Z0001903	STRUCT STEEL REMOV	POUND	13,700.000				
Z0003615	REM EX CONC I-BEAM	EACH	14.000				
Z0012754	STR REP CON DP = < 5	SQ FT	173.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	20.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	10.000				
Z0016200	DECK SLAB REP (PART)	SQ YD	50.000				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	8.000				
Z0023600	FILL EXIST CULVERTS	EACH	2.000				
Z0032300	JACK EXIST SUP-STR	L SUM	1.000				
Z0034105	MATL TRANSFER DEVICE	TON	14,926.000				
Z0076600	TRAINEES	HOUR	2,000.000		0.800		1,600.000
Z0076604	TRAINEES TPG	HOUR	2,000.000		10.000		20,000.000
20200100	EARTH EXCAVATION	CU YD	514.000				
20400800	FURNISHED EXCAVATION	CU YD	573.000				
20700110	POROUS GRAN EMBANK	TON	50.000				
20800150	TRENCH BACKFILL	CU YD	46.000				
25000200	SEEDING CL 2	ACRE	0.900				
25000400	NITROGEN FERT NUTR	POUND	90.000				
25000500	PHOSPHORUS FERT NUTR	POUND	90.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000600	POTASSIUM FERT NUTR	POUND	90.000				
25000700	AGR GROUND LIMESTONE	TON	2.000				
25100115	MULCH METHOD 2	ACRE	0.900				
28000250	TEMP EROS CONTR SEED	POUND	100.000				
28000400	PERIMETER EROS BAR	FOOT	2,754.000				
28100107	STONE RIPRAP CL A4	SQ YD	736.000				
28200200	FILTER FABRIC	SQ YD	736.000				
31101000	SUB GRAN MAT B	TON	552.100				
35501319	HMA BASE CSE 8 3/4	SQ YD	728.000				
35501324	HMA BASE CSE 10	SQ YD	652.000				
35501341	HMA BASE CSE 14 1/4	SQ YD	715.000				
40600300	AGG PR CT	TON	26.800				
40600837	P LEV BIND MM N70	TON	707.000				
40600895	CONSTRUC TEST STRIP	EACH	4.000				
40600982	HMA SURF REM BUTT JT	SQ YD	2,952.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 72C90

State Job # - C-96-085-09

County Name - SANGAMON- -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600990	TEMPORARY RAMP	SQ YD	2,230.000				
40603235	P HMA BC IL19.0 N70	TON	2,308.000				
**DEL 40603240	<del>P HMA BC IL19.0 N90</del>	<del>TON</del>	<del>40,464.000</del>				
**ADD 40603243	P HMA BC IL19.0FGN90	TON	40,464.000				
40603515	P HMA SC "C" N70	TON	1,200.000				
40603545	P HMA SC "D" N90	TON	15,304.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	75.000				
42001500	PCC BR APPR SHLD PAVT	SQ YD	134.000				
44000100	PAVEMENT REM	SQ YD	736.000				
44000151	HMA SURF REM 1/2	SQ YD	77,678.000				
44000152	HMA SURF REM 3/4	SQ YD	11,354.000				
44000155	HMA SURF REM 1 1/2	SQ YD	27,233.000				
44000159	HMA SURF REM 2 1/2	SQ YD	2,863.000				
44000161	HMA SURF REM 3	SQ YD	2,293.000				
44000162	HMA SURF REM 3 1/4	SQ YD	101,362.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000167	HMA SURF REM 4 1/2	SQ YD	80,387.000				
44000500	COMB CURB GUTTER REM	FOOT	6,956.400				
44003100	MEDIAN REMOVAL	SQ FT	633.200				
44004250	PAVED SHLD REMOVAL	SQ YD	100.000				
44200525	CL A PATCH T1 8	SQ YD	30.000				
44200529	CL A PATCH T2 8	SQ YD	60.000				
44200929	CL B PATCH T1 8	SQ YD	20.000				
44200934	CL B PATCH T2 8	SQ YD	40.000				
44201299	DOWEL BARS 1 1/2	EACH	170.000				
44201741	CL D PATCH T2 8	SQ YD	95.000				
44201745	CL D PATCH T3 8	SQ YD	70.000				
44201747	CL D PATCH T4 8	SQ YD	100.000				
*ADD 44213000	PATCH REINFORCEMENT	SQ YD	90.000				
44213100	PAVEMENT FABRIC	SQ YD	150.000				
44213200	SAW CUTS	FOOT	1,400.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44213204	TIE BARS 3/4	EACH	6.000				
48102100	AGG WEDGE SHLD TYPE B	TON	12,245.000				
48203042	HMA SHOULDERS 11 1/4	SQ YD	60.000				
48203047	HMA SHOULDERS 12 1/2	SQ YD	40.000				
48203100	HMA SHOULDERS	TON	17,069.000				
50102400	CONC REM	CU YD	107.200				
50104650	SLOPE WALL REMOV	SQ YD	18.000				
50104720	REM EXIST CONC DECK	EACH	2.000				
50105220	PIPE CULVERT REMOV	FOOT	236.000				
50157300	PROTECTIVE SHIELD	SQ YD	1,405.000				
50300225	CONC STRUCT	CU YD	176.500				
50300255	CONC SUP-STR	CU YD	1,572.700				
50300260	BR DECK GROOVING	SQ YD	2,794.000				
50300300	PROTECTIVE COAT	SQ YD	5,095.000				
50400805	F & E P P CON I-BM 36	FOOT	370.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50500405	F & E STRUCT STEEL	POUND	26,670.000				
50500505	STUD SHEAR CONNECTORS	EACH	3,366.000				
50800205	REINF BARS, EPOXY CTD	POUND	385,870.000				
50800515	BAR SPLICERS	EACH	538.000				
51100100	SLOPE WALL 4	SQ YD	18.000				
51500100	NAME PLATES	EACH	2.000				
52000110	PREF JT STRIP SEAL	FOOT	342.000				
*ADD 52100010	ELAST BEARING ASSY T1	EACH	36.000				
*DEL 52100110	FUR ELAST BRNG ASY T1	EACH	36.000				
52100520	ANCHOR BOLTS 1	EACH	72.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	18.000				
52100540	ANCHOR BOLTS 1 1/2	EACH	18.000				
542A0217	P CUL CL A 1 12	FOOT	88.000				
54215547	MET END SEC 12	EACH	8.000				
58700300	CONCRETE SEALER	SQ FT	2,847.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
59300100	CONTR LOW-STRENG MATL	CU YD	9.000				
60260100	INLETS ADJUST	EACH	2.000				
60500305	FILL INLETS	EACH	6.000				
60608600	COMB CC&G TM6.06	FOOT	5,494.100				
60610400	COMB CC&G TM6.24	FOOT	144.200				
60618300	CONC MEDIAN SURF 4	SQ FT	11,460.100				
*DEL 60622400	<del>CONC MED TSM6.06</del>	<del>SQ FT</del>	<del>3,496.100</del>				
60900315	TY D INLET BOX 609006	EACH	8.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	525.000				
63100085	TRAF BAR TERM T6	EACH	6.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	6.000				
63200310	GUARDRAIL REMOV	FOOT	1,238.000				
63301210	REM RE-E SPBGR TY A	FOOT	175.000				
63301990	REM RE-E T B TERM T1	EACH	2.000				
63302700	REM RE-E T B TERM T6	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

County Name - SANGAMON - -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63500105	DELINEATORS	EACH	226.000				
64200116	SHOULDER RUM STRIP 16	FOOT	110,303.000				
67000400	ENGR FIELD OFFICE A	CAL MO	8.000				
67100100	MOBILIZATION	L SUM	1.000				
*DEL 70100205	TRAF CONT-PROT 701401	EACH	<del>1.000</del>				
70100310	TRAF CONT-PROT 701421	L SUM	1.000				
70100320	TRAF CONT-PROT 701422	L SUM	1.000				
70100405	TRAF CONT-PROT 701321	EACH	1.000				
*REV 70100420	TRAF CONT-PROT 701411	EACH	8.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100815	TRAF CONT-PROT 701446	L SUM	1.000				
70100820	TRAF CONT-PROT 701451	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	30.000				
70106500	TEMP BR TRAF SIGNALS	EACH	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	16.000				
70200100	NIGHT WORK ZONE LIGHT	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	15,171.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	130.000				
70300230	TEMP PVT MK LINE 5	FOOT	144,033.000				
70300240	TEMP PVT MK LINE 6	FOOT	933.000				
70300250	TEMP PVT MK LINE 8	FOOT	7,100.000				
70300260	TEMP PVT MK LINE 12	FOOT	748.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,009.000				
70400100	TEMP CONC BARRIER	FOOT	1,950.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,925.000				
70600260	IMP ATTN TEMP FRN TL3	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

72C90

State Job # - C-96-085-09

County Name - SANGAMON -

Code - 167 - -

District - 6 - -

Section Number - (84-10-1RS-3,84-10-2RS-4)BR,I

Project Number  
 ACNHPP-0072/401/

Route  
 FAI 72

\* REVISED: OCTOBER 28, 2013

\*\* REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70600332	IMP ATTN REL FRN TL3	EACH	6.000				
78004200	PREF PL PM TB INL L&S	SQ FT	255.000				
78004220	PREF PL PM TB INL L5	FOOT	15,509.000				
78004230	PREF PL PM TB INL L6	FOOT	933.000				
78004240	PREF PL PM TB INL L8	FOOT	7,792.000				
78004250	PREF PL PM TB INL L12	FOOT	902.000				
78004280	PREF PL PM TB INL L24	FOOT	166.000				
78009005	MOD URETH PM LINE 5	FOOT	149,138.000				
78009006	MOD URETH PM LINE 6	FOOT	689.000				
78100100	RAISED REFL PAVT MKR	EACH	2,008.000				
78200300	PRISMATIC CURB REFL	EACH	68.000				
78200410	GUARDRAIL MKR TYPE A	EACH	12.000				
78201000	TERMINAL MARKER - DA	EACH	6.000				
78300200	RAISED REF PVT MK REM	EACH	2,008.000				

21. Pavement patching operations on the interchange ramps shall be completed half lane at a time allowing the ramps to remain open to traffic; therefore, flaggers with use of directional barricades and cones, in accordance with applicable portions off TC&P Standard 701456, shall be used to push traffic over on the shoulders when doing this work. Work on the ramps shall be daytime only.
22. Calcium Chloride Accelerator for Portland Cement Concrete shall be used for pavement patching where only daytime full / partial lane closures are allowed.
23. TR 420 (Overpass Road) and CH 12 (Mechanicsburg Road) will remain open to two-way traffic as detailed in the staging plans while the bridge work is ongoing.
24. Work shall be coordinated, so all lanes (except bridge repair areas) are open for Holidays and Holiday weekends per the Standard Specifications.
25. Traffic Control and Protection (Special) shall be used for all work done under the Maintenance of Traffic (MOT) staging plans for CH 12 and TR 420.
- 26. Cones and/or drums on two lane sections of I-72 shall be removed to allow two open lanes of traffic once binder is placed, and any other times when construction is not anticipated in the next 24 hours.**

#### Lane Closure Restrictions

Two lanes of traffic must be maintained between 2PM – 6PM eastbound and 6AM-9AM westbound from the beginning of the project just west of I 55 (Station 20+48.80) through the CH 12 Mechanicsburg Road interchange (to Station 79+00, approximately 1,000 feet past the interchange).

On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to 6:00 P.M. Sunday, except where special consideration or major rehabilitation makes it impractical. The portion of this project where this is applicable is I 72 from the western project limits to Mechanicsburg Road.

#### Short-Term Closure at I-72 and CH 12 (Exit 104) and I-72 and TR 420 (Exit 108)

The I-72 / CH 12 and I-72 / TR 420 interchange ramps shall be temporarily closed (short-term) to allow the Contractor to place hot-mix asphalt binder and surface courses on the ramp pavements.

Only one pair of ramps at one interchange shall be closed at a time and only between the hours of 9:00 a.m. and 3:00 p.m. Total time of each closure shall not exceed 6 hours with only two closures allowed per ramp.

The Contractor shall notify the Engineer three (3) weeks prior to closure of any ramps.

Traffic Control and Protection Standard 701451 will be required to be used during closure of the ramps. The Engineer will designate the type and placement of the barricades, or as shown in the plans.

Revised 10/30/13