							PAVEMEN	NT MARKING	SCHEDULE							
LOCATION	STATION	то	STATION	LENGTH		THANE PVT MKG- NE 5"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 5"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 6"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 8"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 12"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LTRS. & SYMB.	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PVT MARKER REMOVAL	DELINEATORS	SHORT-TERM PVT MKG	WORK ZONE PVT. MARKIN REM.
				(FT)	WHITE (FT)	YELLOW (FT)	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(EACH)	(EACH)	(EACH)	(FT)	(SQ FT)
2 EB MAINLINE	•			•				•	•				-	•		•
	20+48.80	ТО	28+28.00	779	779	779	390					39	39		218	72
	28+28.00	TO	31+17.00	289		289	145	72				14	14		81	27
	31+17.00	ТО	34+91.00	374		374	187		374	187		19	19		105	35
	34+91.00	TO	58+58.00	2,367	2,367	2,367	1,184					118	118		663	219
	58+58.00	ТО	63+71.00	513		513	257		513			26	26		144	47
	63+71.00	то	70+20.00	649		649	325	162				32	32		182	60
	70+20.00	ТО	90+43.00	2,023	2,023	2,023	1,012				130	101	101		566	187
	90+43.00	ТО	95+93.00	550	550	550	138					14	14		99	33
	95+93.00	ТО	193+22.58	9,730	9,730	9,730	2,432					243	243		1,751	578
	193+22.58	ТО	201+41.40	819	1,024	819	205					20	20		147	49
	201+41.40	ТО	249+63.00	4,822	4,822	4,822	1,205					121	121		868	286
	249+63.00	ТО	252+49.00	286		286	72	72				7	7		51	17
	252+49.00	то	256+31.00	382		382	96		382	187		10	10		69	23
	256+31.00	ТО	280+92.00	2,461	2,461	2,461	615					62	62		443	146
	280+92.00	ТО	286+03.00	511		511	128		511			13	13		92	30
	286+03.00	TO	292+53.00	650		650	163	163				16	16		117	39
	292+53.00	ТО	295+70.43	317	317	317	79					8	8		57	19
2 WB MAINLINE	202 - 00.00		200 170.10		017	017									0,	
	20+48.80	ТО	25+52.13	503	503	503	126		1			13	13		91	30
	25+52.13	ТО	32+04.00	652		652	163	163				16	16		117	39
	32+04.00	TO	37+15.00	511		511	128	100	511			13	13		92	30
	37+15.00	ТО	62+46.00	2,531	2,531	2,531	633					63	63		456	150
	62+46.00	ТО	66+18.00	372	2,001	372	93		372	187		9	9		67	22
	66+18.00	TO	69+08.83	291		291	73	73	512	107		7	7		52	17
	69+08.83	TO	193+37.70	12,429	12,429	12,429	3,107	7.5				311	311		2,237	738
	193+37.70	TO	201+56.53	819	1,024	819	205					20	20		147	49
	201+56.53	TO	241+16.90	3,960	3,960	3,960	990					99	99		713	235
	241+16.90	TO	247+81.08	664	664	5,960 664	166	+		1		17	17		120	39
	247+81.08	ТО	254+13.00	632	004	632	158	158	1	1		16	16		114	38
	254+13.00	TO	259+51.00	538		538	135	130	538			13	13		97	32
	254+13.00	TO	280+33.00	2,082	2,082	2,082	521		550			52	52		375	124
	280+33.00	TO		379	2,002	379	95		379	187		9	9		68	23
			284+12.00					71	3/8	10/			7			
	284+12.00	TO	286+95.94	284	07.	284	71	71				7	· '		51	17
	286+95.94	TO	295+70.43	874	874	874	219		1		1	22	22	l	157	52

USER NAME = sparksgw	DESIGNED -	ВТМ	REVISED -	Γ
	DRAWN -	ВТМ	REVISED -	l
PLOT SCALE = 2.0000 '/ in.	CHECKED -	JSA	REVISED -	l
PLOT DATE = Sep-06-2013 07:48:18AM	DATE -	12/19/12	REVISED -	l

SCALE:

SCHEDULE OF QUANTITIES							SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
							*	SANGAMON	194	27		
						* (84	4-10-1)RS-3, (84-10-2)RS-4	CONTRACT	NO.	2090		
SHEET	NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT						