


EXIST. CURVE C5 (1-72)
 PI STA. = 222+56.58
 $\Delta = 42^\circ 41' 52''$ (RT)
 $D = 2^\circ 00' 00''$
 $R = 2,864.79'$
 $T = 1,119.75'$
 $L = 2,134.89'$
 $E = 211.06'$
 $e = 5.44\%$
 $T.R. = 67.50'$
 $S.E. RUN = 244.50'$
 $P.C. STA. = 211+36.83$
 $P.T. STA. = 232+71.72$

PAVEMENT MARKING LEGEND

- ① PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 5" (30' SKIP, 10' DASH)
- ② PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID YELLOW)
- ③ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID WHITE)
- ④ PR URETHANE PAVEMENT MARKING, LINE 6" (SOLID WHITE)
- ⑤ PR URETHANE PAVEMENT MARKING, LINE 6" (6' SKIP, 2' DASH)
- ⑥ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 8" (SOLID WHITE)
- ⑦ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID WHITE)
- ⑧ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 24" (SOLID WHITE)
- ⑨ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LETTERS & SYMBOLS (SOLID WHITE)
- ▷ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, WHITE
- ◀ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, AMBER



	USER NAME = sparksgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN SHEETS				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
		DRAWN - BTM	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.	I-72	*	SANGAMON	194	43
	PLOT SCALE = 100.0000' / in.	CHECKED - JSA	REVISED -										*	(84-10-1)RS-3, (84-10-2)RS-4	CONTRACT NO. 72C90	
	PLOT DATE = Sep-06-2013 08:16:25AM	DATE - 12/19/12	REVISED -											ILLINOIS FED. AID PROJECT		