

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N. 084-0150	S.N. 084-0151	S.N. 084-0154
51500100	NAME PLATES	EACH	2		1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	342		136	72	134
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	36		18		18
52100520	ANCHOR BOLTS, 1"	EACH	72		36		36
52100530	ANCHOR BOLTS, 1 1/4"	EACH	18		18		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	18				18
54215547	METAL END SECTIONS 12"	EACH	8	8			
58700300	CONCRETE SEALER	SQ FT	2847		2455		392
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	9		5		4
60260100	INLETS TO BE ADJUSTED	EACH	2	2			
60500305	FILLING INLETS	EACH	6	6			
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	5494.1	5494.1			
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	144.2	144.2			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	11460.1	11460.1			

* ITEM REQUIRES SPECIAL PROVISION

USER NAME = sparksgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2.0000' / in.	DRAWN - BTM	REVISED -						1722	*	SANGAMON	194	65
PLOT DATE = Sep-06-2013 09:02:00AM	CHECKED - JSA	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	* (84-10-1RS-3,84-10-2RS-4)BR,I CONTRACT NO. 72C90			
PLOT DATE = Sep-06-2013 09:02:00AM	DATE - 12/19/12	REVISED -		ILLINOIS FED. AID PROJECT (84-10-1,2)RS-3 & (84-10-2)RS-4								