

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N. 084-0150	S.N. 084-0151	S.N. 084-0154
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	10717	10717			
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	354	354			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	54		27		27
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	13700		6800		6900
Z0003615	REMOVAL OF EXISTING CONCRETE I-BEAM	EACH	14		14		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	173		145		28
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	20			20	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10			10	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	50			50	
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	8		4		4
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2			
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	2		1		1
Z0041500	PLUG EXISTING CULVERTS	EACH	8	8			
Z0053700	RESETTING SURVEY MONUMENTS	EACH	1	1			

* ITEM REQUIRES SPECIAL PROVISION

USER NAME = sparksgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2.0000' / in.	DRAWN - BTM	REVISED -						1722	*	SANGAMON	194	69
PLOT DATE = Sep-06-2013 09:04:05AM	CHECKED - JSA	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				* (84-10-1RS-3,84-10-2RS-4)BR,I		CONTRACT NO. 72C90		
PLOT DATE = Sep-06-2013 09:04:05AM	DATE - 12/19/12	REVISED -						ILLINOIS FED. AID PROJECT		(84-10-1,2)RS-3 & (84-10-2)RS-4		