

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | | | |
|----------|--|-------|----------------|---------------------------|--------------------------|--------------------------|--------------------------|
| | | | | 90% FED 10% STATE ROADWAY | 90% FED 10% STATE BRIDGE | 90% FED 10% STATE BRIDGE | 90% FED 10% STATE BRIDGE |
| | | | | 0004 | 0014 | 0014 | 0014 |
| | | | | NONE | S.N.084-0150 | S.N.084-0151 | S.N.084-0154 |
| 50102400 | CONCRETE REMOVAL | CU YD | 107.2 | | 99.2 | 5.4 | 2.6 |
| 50104650 | SLOPE WALL REMOVAL | SQ YD | 18 | | 10 | | 8 |
| 50104720 | REMOVAL OF EXSTING CONCRETE DECK | EACH | 2 | | 1 | | 1 |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 236 | 236 | | | |
| 50157300 | PROTECTIVE SHIELD | SQ YD | 1405 | | 596 | 313 | 496 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 176.5 | | 120.5 | | 56 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 1572.7 | | 810.9 | 5.4 | 756.4 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 2794 | | 1247 | | 1547 |
| 50300300 | PROTECTIVE COAT | SQ YD | 5095 | | 2465 | 26 | 2604 |
| 50400805 | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN. | FOOT | 370 | | 370 | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 26670 | | 12900 | | 13770 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 3366 | | 1656 | | 1710 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 385870 | | 193120 | 1330 | 191420 |
| 50800515 | BAR SPLICERS | EACH | 538 | | 284 | 20 | 234 |

| | | | |
|---|----------------------|------------|-----------|
| FILE NAME : | USER NAME : | DESIGNED : | REVISED : |
| es:\p\work\sporksgw\d022183\0672\08-shc-500.dgn | sporksgw | - | - |
| Default | PLOT SCALE : | CHECKED : | REVISED : |
| | 1/8" = 1'-0" | - | - |
| | PLOT DATE : | DATE : | REVISED : |
| | 8/20/2013 10:44:47AM | - | - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
COMBINED- PARTS "A" & "B"**

SCALE: SHEET OF SHEETS STA. TO STA.

| | | | | |
|---------------------------|---------|----------|--------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1-72 | - | SANGAMON | 194 | 7 |
| ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 72C90 | |

Rev.