

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N.084-0150	S.N.084-0151	S.N.084-0154
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15171	15171			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	130	130			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	144033	144033			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	933	933			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	7100	7100			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	748	748			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5009	5009			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1950	1950			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1925	1925			
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6			
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6			
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	255	255			
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	15509	15509			
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	933	933			

14

* SPECIALTY ITEM

FILE NAME *	USER NAME = sporksg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES COMBINED- PARTS "A" & "B"				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\work\sporksg\0221183\067290-shl-500.dgn	DRAWN -	REVISED -	1-72						*	SANGAMON	194	11	
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 72C90				
	PLOT DATE = Sep-05-2013 10:46:39AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								