

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE	90% FED 10% STATE BRIDGE
				0004	0014	0014	0014
				NONE	S.N. 084-0150	S.N. 084-0151	S.N. 084-0154
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	552.1	552.1			
35501319	HOT-MIX ASPHALT BASE COURSE, 8 3/4"	SQ YD	728	728			
35501341	HOT-MIX ASPHALT BASE COURSE, 14 1/4"	SQ YD	715	715			
X4060115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POLIND	16,696	16,696			
40600300	AGGREGATE (PRIME COAT)	TON	26.8	26.8			
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	687	687			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	352	352			
40600990	TEMPORARY RAMP	SQ YD	725	725			
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2308	2308			
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	741	741			
40603515	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1200	1200			
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	378	378			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	75	75			

Rev.

* ITEM REQUIRES SPECIAL PROVISION

USER NAME : sparksgv PLOT SCALE : 2.0000' / 1" = 1' PLOT DATE : Sep-06-2013 09:08:24AM	DESIGNED - BTM DRAWN - BTM CHECKED - JSA DATE - 12/19/12	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.I. RTE. 1722 SECTION * COUNTY SANGAMON TOTAL SHEETS 194 SHEET NO. 62 * (84-10-1RS-3,84-10-2RS-4) BR. I [ILLINOIS] FED. AID PROJECT (84-10-1,2)RS-3 & (84-10-2)RS-4	CONTRACT NO. 72C90
--	---	--	---	---	---	--------------------