

CONSTR. CODE

100% STATE

ROADWAY

0005

S. N.

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	S. N.
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	206.7	206.7
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	72	72
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	46.7	46.7
44213000	PATCHING REINFORCEMENT	SQ YD	325.3	325.3
44213200	SAW CUTS	FOOT	1,780	1,780
44213204	TIE BARS 3/4"	EACH	18	18
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	10	10
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
X4820110	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	150	150

FILE NAME *	USER NAME * aherptd	DESIGNED - DMS	REVISED -
S:\CONTRMANT_CAD\72629 - 1-55- logan-	Plotting 11-8-2013 letting*3 0672629-shi-500	DRAWN - DMS	REVISED -
Default	PLOT SCALE * 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE * Aug-26-2013 06:23:14AM	DATE - 5-13-2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 PATCH LOGAN CO. 2014	LOGAN	6	3
				CONTRACT NO. 72629
ILLINOIS FED. AID PROJECT				