STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS

LOC	ATION		FOOT
LT	STA 119+04.02	TO STA 119+18.83	25.0
RT	STA 116+39.10	TO STA 116+76.60	37.5
TOT	AL		62.5

TRAFFIC BARRIER TERMINAL, TYPE 6

LOCATION				
LT	STA 116+76.60	TO STA 117+19.75	1	
LT	STA 118+60.20	TO STA 119+04.02	1	
RT	STA 116+76.60	TO STA 117+19.75	1	
RT	STA 118+60.29	TO STA 119+02.86	1	
TOT	AL		4	_

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT				
CATION		EAC		
STA 116+26.60	TO STA 116+76.60			
STA 115+89.10	TO STA 116+39.10			
STA 118+02.86	TO STA 119+52.14			
TOTAL				
	CATION STA 116+26.60 STA 115+89.10 STA 118+02.86	CATION STA 116+26.60 TO STA 116+76.60 STA 115+89.10 TO STA 116+39.10 STA 118+02.86 TO STA 119+52.14		

GUARDRAIL REMOVAL				
LOCATION		FOOT		
LT STA 117+24.59	TO STA 117+63.29	38.70		
LT STA 118+16.75	TO STA 118+43.53	26.78		
RT STA 114+87.17	TO STA 117+63.29	276.12		
RT STA 118+16.71	TO STA 119+90.03	173.32		
TOTAL		514.92		

FURNISHING AND ERECTING RIGHT-OF-WAY M	IARKERS
LOCATION	EACH
30' RT STA 115+70.00	1
80' RT STA 115+70.00	1
30' LT STA 117+50.00	1
50' LT STA 117+50.00	1
60' RT STA 118+20.00	1
80' RT STA 118+20.00	1
30' LT STA 118+65.00	1
50' LT STA 118+65.00	1
60' RT STA 119+60.00	1
30' RT STA 120+00.00	1
TOTAL	10

SHORT-TERM PAVEMENT MARKING LOCATION STA 115+40.00 TO STA 125+32.94 TOTAL

TEMPORARY PAVEMENT MARKING - LINE 4" LOCATION SOLID WHITE EDGE LINE LT STA 115+40.00 TO STA 125+32.94 RT STA 115+40.00 TO STA 125+32.94

DOUBLE YELLOW CENTERLINE STA 115+40.00 TO STA 125+32.94 TOTAL

WORK ZONE PAVEMENT MARKING REMOVAL

200/11011		
STA 115+40.00	TO STA 125+32.94	
TOTAL		

PAINT PAVEMENT MARKING - LINE 4" LOCATION SOLID WHITE EDGE LINE

SOLID WHITE EDGE LINE LT STA 115+40.00 TO STA 125+32.94 RT STA 115+40.00 TO STA 125+32.94

DOUBLE YELLOW CENTERLINE STA 115+40.00 TO STA 125+32.94 TOTAL

RAISED REFLEC	TIVE PAVEMENT MARKER
LOCATION	
STA 115+40.00	TO STA 125+32.94
TOTAL	

GUARDRAIL MARKERS LOCATION LT STA 116+76.60 TO STA 119+18.83 RT STA 116+79.10 TO STA 118+02.86 TOTAL TOTAL

TER	MINAL MARKER - DIRECT APPLIED
LOC	ATION
LT	STA 116+26.60
RT	STA 115+89.10
RT	STA 119+52.14
TOT	AL

	JOB = 2223.5	DESIGNED - NAK	REVISED -			SBI SECTION	COUNTY TOTAL SHEET
		DRAWN - TJD	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES	1B (12A)B-1	WABASH 52 13
	PLOT SCALE = 40.0000 '/ IN.	CHECKED - NAK	REVISED -	DEPARTMENT OF TRANSPORTATION		_	CONTRACT NO. 74217
Civil and Structural Engineering	PLOT DATE = 7/24/2013	DATE - 4/8/2011	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. A	AID PROJECT

FOOT	
100	
100	
FOOT	
1001	
992.94	
992.94	
1,985.88	
3,971.76	
SQ FT	
33.33	
33.33	
00.00	
FOOT	
992.94	
992.94	
1,985.88	
3,971.76	
-,	
EACH	
13	
13	
13	

EACH
4
4
8
EACH
1
1
1

3