

PIPE UNDERDRAINS 6" (SPECIAL)													
LOCATION		PIPE UNDERDRAIN 6" (SPECIAL) (FOOT)	CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	PIPE UNDERDRAIN REMOVAL (FOOT)	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	SHOULDER REMOVAL & REPLACE 5" (FOOT)	LOCATION		PIPE UNDERDRAIN 6" (SPECIAL) (FOOT)	CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	PIPE UNDERDRAIN REMOVAL (FOOT)	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	SHOULDER REMOVAL & REPLACE 5" (FOOT)
STATION	RT/LF						STATION	RT/LF					
I-64 EASTBOUND						I-64 WESTBOUND							
89+10	LEFT	18	1	18	1	10	230+00	RIGHT	18	1	18	1	8
104+60	LEFT	18	1	18	1	10	235+00	RIGHT	18	1	18	1	8
111+00	LEFT	18	1	18	1	10	240+00	RIGHT	18	1	18	1	8
115+00	LEFT	18	1	18	1	10	89+00	LEFT	20	1	20	1	10
121+82	LEFT	18	1	18	1	10	104+60	LEFT	20	1	20	1	10
155+00	LEFT	18	1	18	1	8	111+00	LEFT	20	1	20	1	10
162+00	LEFT	18	1	18	1	8	115+00	LEFT	20	1	20	1	10
167+00	LEFT	18	1	18	1	8	121+95	LEFT	20	1	20	1	8
172+00	LEFT	18	1	18	1	8	124+50	LEFT	20	1	20	1	8
177+00	LEFT	18	1	18	1	8	155+00	LEFT	20	1	20	1	10
182+00	LEFT	18	1	18	1	8	162+00	LEFT	20	1	20	1	10
187+00	LEFT	18	1	18	1	8	167+00	LEFT	20	1	20	1	10
192+00	LEFT	18	1	18	1	8	172+00	LEFT	20	1	20	1	10
194+00	LEFT	18	1	18	1	8	177+00	LEFT	20	1	20	1	10
199+00	LEFT	18	1	18	1	8	182+00	LEFT	20	1	20	1	10
204+00	LEFT	18	1	18	1	8	187+00	LEFT	20	1	20	1	10
209+00	LEFT	18	1	18	1	8	192+00	LEFT	20	1	20	1	10
213+00	LEFT	18	1	18	1	8	194+00	LEFT	20	1	20	1	10
216+50	LEFT	18	1	18	1	8	199+00	LEFT	20	1	20	1	10
220+00	LEFT	18	1	18	1	8	204+00	LEFT	20	1	20	1	10
225+00	LEFT	18	1	18	1	8	209+00	LEFT	20	1	20	1	10
230+00	LEFT	18	1	18	1	8	214+50	LEFT	20	1	20	1	10
235+00	LEFT	18	1	18	1	8	218+00	LEFT	20	1	20	1	10
240+00	LEFT	18	1	18	1	8	225+00	LEFT	20	1	20	1	10
89+15	RIGHT	20	1	20	1	8	230+00	LEFT	20	1	20	1	10
104+60	RIGHT	20	1	20	1	10	235+00	LEFT	20	1	20	1	10
111+00	RIGHT	20	1	20	1	10	240+00	LEFT	20	1	20	1	10
115+00	RIGHT	20	1	20	1	10	18TH ST RAMP "F"						
155+00	RIGHT	20	1	20	1	10	404+77	LEFT	10	1	10	1	4
162+00	RIGHT	20	1	20	1	10	25TH ST RAMP "H"						
167+00	RIGHT	20	1	20	1	10	1+33	RIGHT	16	1	16	1	6
172+00	RIGHT	20	1	20	1	10	6+00	RIGHT	16	1	16	1	6
177+00	RIGHT	20	1	20	1	10	1+33	LEFT	14	1	14	1	4
182+00	RIGHT	20	1	20	1	10	5+00	LEFT	14	1	14	1	4
187+00	RIGHT	20	1	20	1	10	25TH ST RAMP "K"						
192+00	RIGHT	20	1	20	1	10	1+17	RIGHT	16	1	16	1	6
194+00	RIGHT	20	1	20	1	10	4+00	RIGHT	16	1	16	1	6
200+50	RIGHT	20	1	20	1	10	1+17	LEFT	14	1	14	1	4
205+50	RIGHT	20	1	20	1	10	5+00	LEFT	14	1	14	1	4
209+00	RIGHT	20	1	20	1	10	25TH ST RAMP "G"						
213+00	RIGHT	20	1	20	1	10	5+00	RIGHT	16	1	16	1	6
216+00	RIGHT	20	1	20	1	10	5+00	LEFT	14	1	14	1	4
220+00	RIGHT	20	1	20	1	10	25TH ST RAMP "J"						
225+00	RIGHT	20	1	20	1	10	9+24	RIGHT	16	1	16	1	6
230+00	RIGHT	20	1	20	1	10	14+00	RIGHT	16	1	16	1	6
235+00	RIGHT	20	1	20	1	10	10+00	LEFT	14	1	14	1	4
240+00	RIGHT	20	1	20	1	10	IL 111 RAMP "A"						
I-64 WESTBOUND						IL 111 RAMP "B"							
89+05	RIGHT	18	1	18	1	10	9+00	RIGHT	16	1	16	1	6
104+60	RIGHT	18	1	18	1	10	6+00	LEFT	14	1	14	1	4
111+00	RIGHT	18	1	18	1	9	IL 111 RAMP "B"						
115+00	RIGHT	18	1	18	1	10	15+57	RIGHT	16	1	16	1	6
121+90	RIGHT	18	1	18	1	10	20+57	RIGHT	16	1	16	1	6
155+00	RIGHT	18	1	18	1	10	25+57	RIGHT	16	1	16	1	6
162+00	RIGHT	18	1	18	1	8	16+50	LEFT	14	1	14	1	4
167+00	RIGHT	18	1	18	1	8	IL 111 RAMP "C"						
172+00	RIGHT	18	1	18	1	8	8+00	RIGHT	16	1	16	1	6
177+00	RIGHT	18	1	18	1	8	11+50	RIGHT	16	1	16	1	6
182+00	RIGHT	18	1	18	1	8	11+50	LEFT	14	1	14	1	4
187+00	RIGHT	18	1	18	1	8	IL 111 RAMP "D"						
192+00	RIGHT	18	1	18	1	8	5+00	RIGHT	16	1	16	1	6
194+00	RIGHT	18	1	18	1	8	10+00	RIGHT	16	1	16	1	6
199+00	RIGHT	18	1	18	1	8	8+00	LEFT	14	1	14	1	4
204+00	RIGHT	18	1	18	1	8	11+00	LEFT	14	1	14	1	4
208+00	RIGHT	18	1	18	1	8	IL 111 RAMP "E"						
213+00	RIGHT	18	1	18	1	8	8+00	RIGHT	16	1	16	1	6
216+50	RIGHT	18	1	18	1	8	11+00	RIGHT	16	1	16	1	6
220+00	RIGHT	18	1	18	1	8	11+00	LEFT	14	1	14	1	4
225+00	RIGHT	18	1	18	1	8	IL 111 RAMP "E"						
230+00	RIGHT	18	1	18	1	8	11+00	RIGHT	16	1	16	1	6
							11+00	LEFT	14	1	14	1	4
SUBTOTAL:		1288	69	1288	69	615	SUBTOTAL		1014	60	1014	60	434
TOTAL:		2302	129	2302	129	1049							

PIPE UNDERDRAINS						
LOCATION		PIPE UNDERDRAIN 6" (FOOT)	PIPE UNDERDRAIN REMOVAL (FOOT)	SHOULDER REMOVAL & REPLACE 5" (FOOT)		
STATION	RT/LF					
I-64 EASTBOUND						
89+10	TO	94+18	LEFT	508	508	508
96+12	TO	97+83	LEFT	171	171	171
100+85	TO	104+60	LEFT	375	375	375
106+68	TO	119+82	LEFT	1314	1314	1314
121+82	TO	127+25	LEFT	543	543	543
147+90	TO	157+76	LEFT	986	986	986
159+04	TO	244+74	LEFT	8570	8570	8570
89+15	TO	94+55	RIGHT	540	540	540
96+45	TO	97+80	RIGHT	135	135	135
100+70	TO	104+60	RIGHT	390	390	390
106+63	TO	119+71	RIGHT	1308	1308	1308
151+97	TO	157+82	RIGHT	585	585	585
159+08	TO	192+44	RIGHT	3336	3336	3336
199+05	TO	209+06	RIGHT	1001	1001	1001
209+06	TO	217+71	RIGHT	865	865	865
217+71	TO	244+48	RIGHT	2677	2677	2677
I-64 WESTBOUND						
89+05	TO	93+76	RIGHT	471	471	471
95+74	TO	97+88	RIGHT	214	214	214
100+80	TO	104+60	RIGHT	380	380	380
106+73	TO	119+93	RIGHT	1320	1320	1320
121+90	TO	124+65	RIGHT	275	275	275
151+78	TO	157+51	RIGHT	573	573	573
159+01	TO	245+12	RIGHT	8611	8611	8611
89+00	TO	93+38	LEFT	438	438	438
95+38	TO	97+27	LEFT	189	189	189
100+85	TO	104+60	LEFT	375	375	375
106+78	TO	113+33	LEFT	655	655	655
113+33	TO	119+97	LEFT	664	664	664
121+95	TO	127+88	LEFT	593	593	593
147+58	TO	157+65	LEFT	1007	1007	1007
158+97	TO	205+82	LEFT	4685	4685	4685
205+82	TO	212+94	LEFT	712	712	712
212+94	TO	221+00	LEFT	806	806	806
224+81	TO	245+33	LEFT	2052	2052	2052
18TH ST RAMP "F"						
404+77	TO	408+73	LEFT	396	396	396
25TH ST RAMP "H"						
1+33	TO	9+22	RIGHT	789	789	789
1+33	TO	9+22	LEFT	789	789	789
25TH ST RAMP "K"						
1+17	TO	7+87	RIGHT	670	670	670
1+17	TO	7+87	LEFT	670	670	670
25TH ST RAMP "G"						
1+88	TO	7+49	RIGHT	561	561	561
4+25	TO	7+49	LEFT	324	324	324
8+97	TO	15+55	RIGHT	658	658	658
25TH ST RAMP "J"						
+45	TO	7+76	RIGHT	731	731	731
9+24	TO	13+02	RIGHT	378	378	378
9+24	TO	12+28	LEFT	304	304	