



SUPERSTRUCTURE BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a1(E)	16	#6	24'-2"	—	
a2(E)	16	#6	33'-9"	—	
d(E)	12	#5	4'-4"	┌	
d1(E)	12	#4	4'-1"	┌	
d2(E)	12	#4	3'-2"	┌	
Reinforcement Bars, Epoxy Coated				Pound	1510
Concrete Superstructure				Cu. Yds.	8.7
Concrete Removal				Cu. Yds.	8.8
Preformed Strip Seal				Foot	62

Bars indicated thus 4x2 - #6 etc. indicates 4 lines of bars with 2 lengths per line.

BENTON & ASSOCIATES, INC.

FILE NAME = P:\10e2166-5\ Design\ Plans\ 0820196-76022-004- Deck.dgn	USER NAME =	DESIGNED - MBH	REVISED - 10/3/13
		CHECKED - SJH	REVISED -
		DRAWN - MBH	REVISED -
		CHECKED - SJH	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

CONCRETE REMOVAL & REPLACEMENT STRUCTURE NO. 082-0196

SHEET NO. 4 OF 11 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-2HB-1	ST. CLAIR	208	201
				CONTRACT NO. 76022
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				