

54201

542.01

Designer Note: Do not use this provision without discussing with Operations (Maintenance) to find out if the existing culverts are in good enough condition that they can be reused. This provision does not apply to a "Temporary" pipe culvert that might be specified on your project to be placed in one location then subsequently relocated to another site.

REMOVE AND RELAY PIPE CULVERTS

Effective July 1, 1990

Revised January 1, 2007

The existing pipe culverts, as designated on the plans, shall be removed and re-laid to the lines and grades of the proposed ditches. The Contractor shall use all precautions in removing the pipe. Any pipe damaged by negligence in removing, handling, or relaying shall be replaced by the Contractor at his own expense. The relaying of the pipe shall be done in accordance with the applicable portions of Section 542 of the Standard Specifications.

This work will be paid for at the contract unit price per Foot (Meter) for REMOVE AND RELAY PIPE CULVERTS of the types and diameters specified.