

68000

680.00

Designer Note: Discuss any proposed railroad track or tie removal with Project Support. If work is to be done by our Contractor, include "Railroad Track Removal" and "Railroad Ties Removal and Disposal" special provisions.

RAILROAD TRACK REMOVAL

Effective November 1, 1994

Revised January 1, 2007

This work shall consist of furnishing all labor, equipment and materials required for the removal and disposal off the Right-of-Way of the railroad tracks, ballast, hardware, signals, signal house, signal house foundations, signal foundations, pipe underdrain and PCC curb associated with the crossing at the locations as shown on the plans.

Any holes created by the removal operations shall be backfilled and compacted to the satisfaction of the Engineer.

The Contractor shall take extreme care during the removal operations to keep from disturbing the railroad ties.

Materials resulting from the removal operations shall be disposed of in accordance with Article 202.03 of the Standard Specifications.

The measurement for payment will be per foot (meter) measured down the centerline of the railroad tracks.

This work will be paid for at the contract unit price per Foot (Meter) for RAILROAD TRACK REMOVAL and no additional compensation will be allowed. Removal of the railroad ties and disposal is covered elsewhere in the special provisions.