

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE	
				SAFETY	BRIDGE
				0021	0059
				URBAN	S.N. 016-0855
20200100	EARTH EXCAVATION	CU YD	17	17	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	38	38	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1	
* 25200110	SODDING, SALT TOLERANT	SQ YD	38	38	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	350		350
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	490		490
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	8		8
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	77		77
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1227	1227	
* 42400800	DETECTABLE WARNINGS	SQ FT	89	89	
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	42		42
44000600	SIDEWALK REMOVAL	SQ FT	1094	1094	

* SPECIALTY ITEM
** 0042

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE	
				SAFETY	BRIDGE
				0021	0059
				URBAN	S.N. 016-0855
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	18		18
50102400	CONCRETE REMOVAL	CU YD	22.4		22.4
50104000	BRIDGE RAIL REMOVAL	FOOT	60		60
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22.2		22.2
50300260	BRIDGE DECK GROOVING	SQ YD	967		967
50300300	PROTECTIVE COAT	SQ YD	1203	188	1015
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2470		2470
50800105	REINFORCEMENT BARS	POUND	270		270
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3080		3080
50800515	BAR SPLICERS	EACH	26		26
50900105	ALUMINUM RAILING, TYPE L	FOOT	60		60
52000110	PREFORMED JOINT STRIP SEAL	FOOT	140		140
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	33		33
54003000	CONCRETE BOX CULVERTS	CU YD	1.1		1.1

MODEL: Default
FILE NAME: P11710-746 DOT District 11W0 11 Grand Ave @ DesPlaines RiverCADD Sheets\Cu\1160667-SHT03-S001.dgn



USER NAME = Ken.drabant	DESIGNED - KJD	REVISED -
	DRAWN - KJD	REVISED -
PLOT SCALE = 40.0000' / in.	CHECKED - RTB	REVISED -
PLOT DATE = 8/14/2019	DATE - 08/09/2019	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
GRAND AVENUE OVER DES PLAINES RIVER**

SCALE: 40.0000' / in SHEET 1 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1376	136A-BR(11)	COOK	59	3
			CONTRACT NO. 60R67	
[ILLINOIS FED. AID PROJECT]				

REV. 10/28/19 REV. 9/30/19 REV. 9/12/19