

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT		0047 FED 80% STATE 20%														
28100105	STONE RIPRAP, CLASS A3	SO YD	27	27														
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	126	126														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	279	279														
40604062	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "D", N70	TON	28	28														
50102400	CONCRETE REMOVAL	CU YD	13	13					*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3880	3880				
50157300	PROTECTIVE SHIELD	SO YD	260	260														
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11	11						*	78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	350	350			
50300260	BRIDGE DECK GROOVING	SO YD	685	685														
50300300	PROTECTIVE COAT	SO YD	732	732						*	78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	9	9			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1890	1890							X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	4185	4185			
50800515	BAR SPLICERS	EACH	24	24							X5870015	BRIDGE DECK CONCRETE SEALER	SO FT	1100	1100			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86	86							X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	5	5							X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	6250	6250			
63302400	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS TYPE 5	EACH	2	2							Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SO YD	705	705			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
63302400	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS TYPE 6	EACH	2	2														
67100100	MOBILIZATION	L SUM	1	1														
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	6250	6250														

685 685



FILE NAME =	USER NAME = mdyja	DESIGNED -	REVISED -
pw:\planroom\dtd\illinois\gov\PIWDOT\Documents\VDOT	Offices\Ofstr\cl\NProjects\DI35618\CADD\td\Des\gn\DI35618	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 8/16/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 1 OF 2 SHEETS
STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	2018-053-B-R	COOK	32	3
CONTRACT NO. 62094				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

REV. 10-24-2019 REV. - MS