

CONSTRUCTION CODES

STP URBAN FUNDING

STATE FUNDING

NON-PART.

75% FEDERAL / 25% LOCAL

100% STATE

100% LOCAL

\*THIS DESIGNATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MAIN STREET (FAP 524)		MAIN STREET (FAU 1442)		IL ROUTE 31 (FAU 3887)		TRAINEES 0042	IL ROUTE 31		WATER AND SANITARY
				ROADWAY RECON 0004	SAFETY 0021	ROADWAY RECON 0004	SAFETY 0021	ROADWAY RECON 0004	SAFETY 0021		SAFETY 0021	SAFETY 0021	
* X6022820	MANHOLES, SANITARY, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6										6
* X6026623	VALVE BOX	EACH	7										7
* X6026624	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	10										10
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	6,337	5,631		706							
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.60		0.10		0.30					
X7011006	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0.90		0.10							
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	2,206		137							2,069	
* X8100105	CONDUIT SPLICE	EACH	2									2	
* X8210005	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	10									10	
* X8250060	TEMPORARY LIGHTING CONTROLLER	EACH	1									1	
* X8250091	COMBINATION LIGHTING CONTROLLER	EACH	1									1	
* X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	24									24	
* X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1									1	
* X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	1,422									1,422	
* X8770134	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT. (SPECIAL)	EACH	2										2
* X8770135	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT. (SPECIAL)	EACH	1										1
* X8772860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT. (SPECIAL)	EACH	1										1
* XX001164	LUMINAIRE, HIGH PRESSURE SODIUM, SPECIAL	EACH	4									4	

\*THIS DESIGNATES SPECIALTY ITEMS

PLOT DRIVER = ...\\p\p\dms02314\...pdf.plt  
 PEN TABLE = ...\\p\p\dms02314\...general.tbl  
 FILE NAME = ...\\3184-ah-80016.dgn



USER NAME = mjp	DESIGNED - MJP	REVISED - 10-23-19
PLOT SCALE = 1.0000' / 1in.	DRAWN - MJP	REVISIONS -
PLOT DATE = 8/28/2019	CHECKED - DNM	REVISIONS -
	DATE - 08/28/19	REVISIONS -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

MAIN STREET RECONSTRUCTION  
 SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET OF SHEETS STA. TO STA.

F.A.P./F.A.U. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24/1442 12-00073-02-FP	KANE	207	19
CONTRACT NO. 61F32		ILLINOIS FED. AID PROJECT	