

DATE	
BY	
SUBMITTED	
ALIGNED	
CHECKED	
DATE	
BY	
PLAN	
NOTE BOOK	
NO.	

DATE	
BY	
REVISIONS	
PLANNED	
CHECKED	
DATE	
BY	
PROFILE	
NOTE BOOK	
NO.	

HRG PROJECT NO.: 160444  
 HRG PROJ. CONTACT:  
 FILE NAME: 160444-01-1-sum.dgn  
 PLOT DRIVER: IL\_PLOT\_CW-DWT-FG  
 PEN TABLE: 2019tbl.rlt

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY HSIP 90% FED 10% TWP 0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	148	148
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	396	396
20200100	EARTH EXCAVATION	CU YD	10,928	10,928
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	2,718	2,718
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2,327	2,327
+ 25000210	SEEDING, CLASS 2A	ACRE	3.50	3.50
+ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	315	315
+ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	315	315
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	329	329
28000305	TEMPORARY DITCH CHECKS	FOOT	450	450
28000400	PERIMETER EROSION BARRIER	FOOT	397	397
* 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	100	100
* 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	11,860	11,860
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	24,461	24,461
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	2,447	2,447
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,563	1,563
① 40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	1,247	1,247
44000100	PAVEMENT REMOVAL	SO YD	10,872	10,872
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	763	763
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SO YD	3,810	3,810
52200800	SEGMENTAL CONCRETE BLOCK WALL	SO FT	6,133	6,133
54262815	METAL FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	8	8
542C5470	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	160	160
67100100	MOBILIZATION	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,626	2,626
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	876	876
+ 72000100	SIGN PANEL - TYPE 1	SO FT	126	126
+ 72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	90	90
+ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	266	266
+ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26,260	26,260
+ X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	1	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY HSIP 90% FED 10% TWP 0005
* + X2200020	FENCE REMOVAL AND REINSTALLATION	FOOT	1,225	1,225
* + X2511630	EROSION CONTROL BLANKET (SPECIAL)	SO YD	15,915	15,915
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10
* X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
* Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SO YD	876	876
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
* Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	156	156
+ X1009335	STEEL-BACKED TIMBER GUARDRAIL	FOOT	421	421
+ X1009336	STEEL-BACKED TIMBER, TL-2 END TERMINAL	EACH	4	4

\* SPECIAL PROVISION  
 + SPECIALTY ITEM

HRGreen.com <small>Illinois Professional Design Firm # 184-001922</small>	USER NAME = bhar.tma	DESIGNED - BH	REVISED - 11/1/2019	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> <b>LILY LAKE ROAD</b>				F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	CHECKED - AC	REVISED -		3858	17-14172-01-SP	MCHENRY	51	4				
	PLOT DATE = 11/1/2019	DATE - 8/25/2019	REVISED -		SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 61F99				