

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
- 3-4 SUMMARY OF QUANTITIES
- 5-6 TYPICAL SECTIONS
- 7 EXISTING SITE AND REMOVAL PLAN
- 8 PROPOSED SITE AND PAVEMENT MARKING PLAN
- 9 GRADING PLAN AND LANDSCAPING PLAN
- 10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
- 11 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)

GENERAL NOTES

- 1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
- 2. THE CONTRACTOR SHALL COORDINATE ACTIVITIES WITH THE DISTRICT BRIDGE TEAM OPERATION SUPERVISOR JOHN R. BILSKI AT (847) 956-1444.
- 3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 5. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- 6. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENTIONS.
- 7. EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.
- 8. CONTRACTOR IS TO PERFORM THEIR OPERATIONS DURING THE DISTRICT BRIDE MAINTENANCE YARD OPERATING HOURS, UNLESS APPROVED BY THE TEAM SECTION TECHNICIAN.
- 9. BEFORE COMMENCING ANY WORK, THE CONTRACTOR MUST CONTACT IDOT DISTRICT 1 ELECTRICAL MAINTENANCE CONTRACTOR (EMC) MEADE ELECTRIC - TED TROYNER, 1-708-588-2544 FOR IDOT OWNED UNDERGROUND LIGHTING FACILITIES (CABLES, CONDUITS ETC.) IDENTIFICATION.

LIST OF HIGHWAY STANDARDS

- 000001-08 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE
- 701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701901-09 TRAFFIC CONTROL DEVICES

COMMITMENTS

NO COMMITMENTS FOR THIS PROJECT



- 10. THE AGGREGATE GRADATION FOR THE AGGREGATE SUBGRADE IMPROVEMENT 12" LOWER 9 INCHES SHALL BE CS 1 OR RR 1.
- 11. GEOTECHNICAL FABRIC FOR GROUND STABILIZATION AND/OR AGGREGATE SUBGRADE IMPROVEMENT (CU YD) HAS BEEN PROVIDED FOR USE AT THE LOCATIONS INDICATED FOR SOILS THAT TEND TO BE UNSTABLE AND/OR UNSUITABLE. THE ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH ABOVE ITEM WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE GEOTECHNICAL ENGINEER. ALL POTENTIALLY UNSTABLE SOILS SHOULD BE TESTED WITH A STATIC OR DYNAMIC CONE PENETROMETER AND TREATED IN ACCORDINACE WITH ARTICLE 301.04 OF THE STANDARD SPECIFICATIONS AND IDOT SUBGRADE STABILITY MANUAL. IF UNSTABLE AND/OR UNSUITABLE SOILS ARE NOT ENCOUNTERED, THEN THE QUANTITY SHALL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE DUE TO THE CONTRACTOR.
- 12. THE SUBGRADE STABILITY SHALL BE VERIFIED BY PROOF ROLLING WITH A FULLY LOADED TANDEM-AXLE TRUCK.
- 13. ANY AGGREGATE SUBGRADE CONTAMINATED AND/OR DAMAGED BY THE CONTRACTOR'S VEHICLES AND/OR EQUIPMENT IS TO BE REMOVED AND REPLACED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.

MODEL: D:\62W03-General Notes - 001
FILE NAME: P:\2019\ME\9003_Ver\6a_Phil\W046_02\W03_Blastfield Maint Yard-Bridge\00-CADD\10.12 ORD\CADD\Drawl\Sheets\02-D\62W03-General Notes.dgn

REVISED SHEET 10/21/2024



USER NAME = jpham	DESIGNED - TN	REVISED -
	DRAWN - JP	REVISED -
PLOT SCALE = 0.16866667' / in.	CHECKED - JC	REVISED -
PLOT DATE = 6/12/2024	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
DISTRICT BRIDGE MAINTENANCE YARD**

SCALE: 1"=1'-0" SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1735	2023 DB YARD PARKING	COOK	11	2
CONTRACT NO. 62W03			ILLINOIS FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				URBAN	
				100% STATE	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4	
20200100	EARTH EXCAVATION	CU YD	2413	2413	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1206	1206	⚠
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	259	259	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3620	3620	⚠
25200110	SODDING, SALT TOLERANT	SQ YD	259	259	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1206	1206	⚠
28000510	INLET FILTERS	EACH	7	7	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	14477	14477	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	32452	32452	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	5139	5139	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2506	2506	
42000060	WELDED WIRE REINFORCEMENT	SQ YD	506	506	⚠
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	1496	1496	
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	506	506	
42001300	PROTECTIVE COAT	SQ YD	517	517	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	100	
44000100	PAVEMENT REMOVAL	SQ YD	14984	14984	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1579	1579	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1755	1755	
44000600	SIDEWALK REMOVAL	SQ FT	100	100	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1206	1206	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4	
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1	
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1	
66901005	ENGINEERED BARRIER	SQ YD	590	590	
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	8	8	
67100100	MOBILIZATION	L SUM	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2218	2218	
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	50	50	

* SPECIALTY ITEM

⚠ REVISED SHEET 10/21/2024

MODEL: D:\62W03-SQC-001
FILE NAME: P:\2019\ME\9003_Ver\6r_P\11\W046_62W03_Biesterfeld_Maint_Yard-Fridge\00-CADD\10_12_ORD\CADD_Detail\Sheets\03-D\62W03-SQC-001.dgn



USER NAME = jpham	DESIGNED - TN	REVISED -
	DRAWN - JP	REVISED -
PLOT SCALE = 0.16666667 / in.	CHECKED - JC	REVISED -
PLOT DATE = 7/26/2024	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
DISTRICT BRIDGE MAINTENANCE YARD

SCALE: 1"=1'-0" SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1735	2023 DB YARD PARKING	COOK	11	3
CONTRACT NO. 62W03			ILLINOIS FED. AID PROJECT	

REV-SEP