



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 31, 2024

SUBJECT FAU Route 1292 (IL 53)  
Project NHPP-8Z8C(183)  
Section (531-2-HB)BR 23  
Cook County  
Contract No. 62W30  
Item No. 19, November 8, 2024 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 134 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

Method of Measurement. This work shall be measured and paid for in place, the area computed in square yards of projected concrete surface area formed with bevels and concrete form liners, and colored as specified herein. The pay area for ARCHITECTURAL FORM LINER shall be the projected area from outside edge to outside edge of the bevels, including the recessed letters, measured in square feet. The cost of the typical reveals, including concrete stain, shall be included in this pay item but shall not be measured separately for payment.

Basis of Payment. The form lined surfaces for the Street Name Sign Panel will be paid for at the Contract unit price per square yard for ARCHITECTURAL FORM LINER

### **CONCRETE COLOR ADDITIVE**

Description. This work consists of furnishing all aspects necessary for integrally colored concrete, including but not limited to pigment material purchase and acquisition, delivery of pigment material to redi-mix concrete plant, batch mixing of pigment material, and delivery of integrally colored concrete to the jobsite. The concrete for the parapet walls on the bridge deck superstructure and the bridge approach pavement shall be integrally colored concrete. The work shall conform to applicable portions of Section 503 of the Standard Specifications except as herein modified.

Submittals. Color samples for pigment selection shall be submitted **to the Engineer for approval** as coordinated with the City of Rolling Meadows. The exact pigment selected shall be approved by the Engineer prior to purchasing, mixing, and installation. The integrally colored concrete parapet walls shall **match, to the extent possible**, to the following color (R-G-B): 232-226-217.

Requirements. The cast concrete mockup wall shall be comprised of the selected integrally colored concrete. It shall be the responsibility of the Contractor to protect the adjacent concrete items from any discoloration as a result of contact with the coloring agent or integrally colored concrete.

Method of Measurement and Basis of Payment. This work shall be paid for at the contract unit price per CU YD for CONCRETE COLOR ADDITIVE, which price shall include all labor, materials, and equipment necessary to color the concrete.

### **CONCRETE MEDIAN SURFACE, CORRUGATED**

Description. This work shall consist of constructing a concrete median with special dimensions.

General. This work shall be according to Section 606 of the Standard Specifications.

The concrete median shall be constructed according to the locations and details shown in the drawings.

Method of Measurement. CONCRETE SURFACE, CORRUGATED of the type specified will be measured for payment in place per square foot.

Basis of Payment. This work will be paid for at the contract unit price per square foot for CONCRETE SURFACE, CORRUGATED of the type specified.

Revised 10/31/2024