



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 28, 2024

SUBJECT FAP Route 336A (IL 31)
Section 2024-989-ATR
McHenry County
Contract No. 62X14
Item No. 27, November 8, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page 9 of the Special Provisions
3. Revised sheets 3-8, 23, 24, 27, 30, 31, 34, 38, & 39 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TREE REMOVAL (3 TO 6 UNITS DIAMETER)

This work consists of removing trees 3 units to 6 units diameter defined as saplings. This work shall be done in accordance with Section 201 of the Standard Specifications for tree removal, except that stumps are to be removed to a minimum of six (6) inches below the natural surface of the ground.

Any tree to be removed that is trapped within the access control fence shall be cut flush with the fence. The stump shall be treated with a resprout herbicide approved by the Engineer to prevent regrowth from those stumps.

All references to tree removal in the Standard Specifications shall include the item TREE REMOVAL (SPECIAL). All of the trees to be removed shall be designated by the Engineer.

Basis of Payment: This work will be paid for at the contract unit price per unit diameter for TREE REMOVAL (SPECIAL). No payment for TREE REMOVAL (SPECIAL) will be made until the tree and stump have been completely removed, or in the case of a trapped tree in the access control fence, until the stump has been treated with an approved resprout herbicide.

TRAFFIC CONTROL PLAN (D-1)

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS:

701001, 701006, 701101, 701106, 701201, 701301, 701306, 701311, 701336, 701426, 701501, 701502, 701601, 701606, 701701, 701901

DETAILS:

TC-10: TRAFFIC CONTROL AND PROTECTION FOR SIDES ROADS, INTERSECTIONS, AND DRIVEWAYS

TC-22 -ARTERIAL ROAD INFORMATION SIGN

Revised 10/28/2024