



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 22, 2024

SUBJECT Various Routes  
Section (21BZ-1-1213) BP24  
Cook County  
Contract No. 62X19  
Item No. 28, November 8, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Revised page 7 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF IMPROVEMENT .....	1
DESCRIPTION OF IMPROVEMENT.....	1
STATUS OF UTILITIES (D1).....	2
TRAFFIC CONTROL PLAN .....	5
MAINTENANCE OF ROADWAYS (D1) .....	6
PUBLIC CONVENIENCE AND SAFETY (D1) .....	6
ENGINEER'S FIELD OFFICE TYPE A (D1) .....	7
CONTRACTOR COOPERATION .....	7
<b>RESTRICTIVE START DATE</b> .....	7
BRIDGE WASHING .....	8
DEBRIS REMOVAL (SPECIAL).....	9
CHAIN LINK FABRIC SPECIAL.....	9
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES .....	10
CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES.....	16
CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES.....	41
COMPENSABLE DELAY COSTS (BDE).....	57
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) .....	60
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	62
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE).....	72
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	72
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	74
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	77
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	77
SUBMISSION OF PAYROLL RECORDS (BDE).....	78
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	79
WEEKLY DBE TRUCKING REPORTS (BDE).....	79
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	79
WORKING DAYS (BDE) .....	81

Revised 10/22/2024

**ENGINEER'S FIELD OFFICE TYPE A (D1)**

Effective: January 1, 2022

Revise the first paragraph of Article 670.02 to read:

**670.02 Engineer's Field Office Type A (D1).** Type A (D1) field offices shall have a ceiling height of not less than 7 feet and a floor space of not less than 1000 square feet with a minimum of two separate offices. The office shall also have a separate storage room capable of being locked for the storage of the nuclear measuring devices. The office shall be provided with sufficient heat, natural and artificial light, and air conditioning. Doors and windows shall be equipped with locks approved by the Engineer.

Add the following to Article 670.07 Basis of Payment.

The building or buildings, fully equipped, will be paid for at the contract unit price per calendar month or fraction thereof for ENGINEER'S FIELD OFFICE, TYPE A (D1).

**CONTRACTOR COOPERATION**

It is anticipated that this contract will be constructed simultaneously with other roadway projects in the same area. The projects that may be concurrent with this project are:

**62P69 – Foster Ave Over North Branch Chicago River / Cook County, S.N. 016-0249 & S.N. 016-0250.**

**Bridge Deck Overlay and Bridge Joint Repair.**

**September 2024 letting, Construction expected to begin in April of 2025**

The IDOT Contractor for this contract shall schedule her/ his work to minimize any conflicts that may arise between contracts, as specified in Article 105.08 of the Standard Specifications. No additional compensation will be allowed for delays or inconveniences resulting from activities of other contractors.

**RESTRICTIVE START DATE**

No Bridge painting work will be permitted prior to April 13, 2026. Temporary lane closures for any advance work may be allowed at the discretion of the Engineer.

Revised 10/22/2024