

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE	100% WEST DUNDEE	100% WEST DUNDEE
				ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAFFIC SIGNAL INTERCONNECT 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION (EVP) 0021
			<i>URBAN</i>					
35300415	PORTLAND CEMENT CONCRETE BASE COURSE, 9 3/4"	SQ YD	2,136	2,136				
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 8"	SQ YD	226	226				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	38	38				
35501316	HOT MIX ASPHALT BASE COURSE, 8"	SQ YD	429	429				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.1	19.1				
40600300	AGGREGATE (PRIME COAT)	TON	86	86				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	217	217				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HMA SURFACE REMOVAL - BUTT JOINT	SQ YD	107	107				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2,629.5	2,629.5				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	52	52				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,045	2,045				
42001300	PROTECTIVE COAT	SQ YD	214	214				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	48	48				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	166	166				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	29,313.0	29,313.0				
42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SQ FT	705.0	705.0				
42400410	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	SQ FT	3,441.5	3,441.5				
42400800	DETECTABLE WARNINGS	SQ FT	301	301				
44000100	PAVEMENT REMOVAL	SQ YD	1,974	1,974				

* SPECIALTY ITEM



USER NAME * #USER#	DESIGNED <i>ESJ</i>	REVISED -
PLOT SCALE * #SCALE#	DRAWN <i>ESJ</i>	REVISED -
PLOT DATE * #DATE#	CHECKED <i>GJS</i>	REVISED -
	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 11 SHEETS STA. TO STA.

F.A.U. RTE. 3887	SECTION S-N	COUNTY KANE	TOTAL SHEETS 153	SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A95	