

PROPOSED EARTHWORK SCHEDULE - STAGE 1 (IL 31) (1 OF 2)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
203+50	204+00	50	17.4		0	
204+00	204+50	50	17.5	32.31	0.3	0.28
204+50	205+00	50	13.4	28.6	0.6	0.83
205+00	205+12.43	12.43	13.6	25.0	1.2	1.67
205+12.43	205+50	37.57	9.6	5.3	1.2	0.55
205+50	206+00	50	16.4	18.1	1.4	1.81
206+00	206+34.92	34.92	23.2	36.7	3.6	4.63
206+34.92	206+50	15.08	29.9	34.3	0	2.33
206+50	207+00	50	37.7	18.9	0	0.00
207+00	207+50	50	40.9	72.8	3.4	3.15
207+50	208+00	50	54	87.9	13.1	15.28
208+00	208+50	50	57.7	103.4	10.3	21.67
208+50	208+72.78	22.78	39	89.5	12	20.65
208+72.78	209+00	27.22	19	24.5	0	5.06
209+00	209+50	50	38	28.7	1.6	0.81
209+50	210+00	50	27.8	60.9	10.1	10.83
210+00	210+50	50	22.9	46.9	7.4	16.20
210+50	211+00	50	32.4	51.2	0	6.85
211+00	211+32.45	32.45	31.4	59.1	0.1	0.09
211+32.45	211+50	17.55	44.7	45.7	2.1	1.32
211+50	213+50	200	44.5	29.0	4.5	2.14
213+50	214+00	50	33.6	289.3	2.3	25.19
214+00	214+50	50	32.2	60.9	0.9	2.96
214+50	214+70.16	20.16	27.6	55.4	1.4	2.13
214+70.16	215+00	29.84	29.1	21.2	0.7	0.78
215+00	215+50	50	28.7	31.9	1.4	1.16
215+50	216+00	50	27.6	52.1	0.2	1.48
216+00	216+13.25	13.25	10.8	35.6	0.1	0.28
216+13.25	216+50	36.75	10.3	5.2	0.1	0.05
216+50	217+00	50	26.5	25.0	0	0.07
217+00	217+50	50	25.8	48.4	2.4	2.22
217+50	218+00	50	26.6	48.5	1.5	3.61
218+00	218+16.41	16.41	26.2	48.9	0	1.39
218+16.41	218+50	33.59	23.6	15.1	0	0.00
218+50	219+00	50	17	25.3	4.8	2.99
219+00	219+50	50	21.2	35.4	1.5	5.83
219+50	219+64.51	14.51	23.1	41.0	0.1	1.48
219+64.51	220+00	35.49	13	9.7	0	0.03
220+00	220+50	50	22.1	23.1	0.1	0.07
220+50	221+00	50	20.2	39.2	0	0.09
SUB TOTALS				1810.1		168.01

PROPOSED EARTHWORK SCHEDULE - STAGE 1 (IL 31) (2 OF 2)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
221+00	221+50	50	11	28.9	0	0.00
221+50	222+00	50	9.5	19.0	0	0.00
222+00	222+50	50	3.6	12.1	0	0.00
222+50	222+66.26	16.26	3	6.1	0	0.00
222+66.26	223+00	33.74	3	1.8	0.1	0.03
223+00	223+00	0	2.3	3.3	0	0.06
SUB TOTALS				71.2		0.09
TOTALS				1881.3		168.1

PROPOSED EARTHWORK SCHEDULE - STAGE 1 (IL 72)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
113+00	113+50	50	17.7		0.2	
113+50	114+00	50	14.7	30.0	0.9	1.0
114+00	114+17.27	17.27	18.7	30.9	0.4	1.2
114+17.27	114+50	32.73	19.1	12.1	0.2	0.2
114+50	115+00	50	16.6	21.6	6.2	3.9
115+00	117+00	200	21.6	35.4	3.4	8.9
117+00	117+31	31.48	95.1	432.2	0.3	13.7
117+31	117+50	19	92.9	424.1	0.2	13.3
117+50	117+72.49	22.49	84.8	62.5	2.0	0.8
117+72.49	118+00	27.51	87.7	71.8	1.4	1.4
118+00	118+25.65	25.65	66.1	78.4	0.0	0.7
118+25.65	118+50	24.35	90.2	74.2	0.0	0.0
118+50	118+88.84	38.84	65.4	70.2	0.5	0.2
118+88.84	119+00	11.16	101.0	119.7	0.0	0.4
119+00	119+42.32	42.32	102.8	42.1	0.0	0.0
119+42.32	119+50	7.68	75.6	139.8	0.0	0.0
119+50	120+00	50	73.7	21.2	0.0	0.0
120+00	120+50	50	53.1	117.4	0.0	0.0
120+50	120+86.94	36.94	38.9	85.2	0.0	0.0
120+86.94	121+00	13.06	0.0	26.6	0.0	0.0
121+00	121+50	50	0.0	0.0	0.0	0.0
121+50	122+00	50	20.9	19.4	0.2	0.2
122+00	122+43.51	43.51	19.3	37.2	0.4	0.6
122+43.51	122+50	6.49	26.6	37.0	0.1	0.4
122+50	123+00	50	27.6	6.5	0.0	0.0
123+00	123+50	50	17.6	41.9	0.1	0.1
123+50	124+00	50	13.0	28.3	1.4	1.4
124+00	124+00	0	12.0	23.1	3.8	4.8
TOTALS				2088.9		53.2



USER NAME = #USER#
 DESIGNED *ESI*
 DRAWN *ESI*
 CHECKED *GJS*
 DATE *07/03/12*

REVISOR -
 REVISIONS -
 REVISIONS -
 REVISIONS -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES
 SCALE: NONE SHEET NO. 2 OF 25 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	19
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				