

PRE-STAGE & STAGE 3 PAVEMENT MARKING SCHEDULE (1 OF 2)

LOCATION	PRE-STAGE 3 REMOVALS									
	70301000					78300100				
	WORK ZONE PVMT MRKING REMOVAL					PVMNT MRKNG REMOVAL				
	4"	6"	12"	24"	LETTERS & SYMBOLS	4"	6"	12"	24"	LETTERS & SYMBOLS
SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	
IL ROUTE 72										
STA 112+69.07 TO STA 124+33.29	1186.0	143.3	0.0	0.0	0.0	44.6	0.0	342.0	140.0	218.4
IL ROUTE 31										
STA 203+19.37 TO STA 211+00.00	735.3	0.0	0.0	0.0	0.0	23.6	0.0	0.0	0.0	72.8
STA 215+00.00 TO STA 223+07.84	679.3	0.0	0.0	0.0	0.0	54.6	82.5	0.0	0.0	145.6
SUB TOTALS	2600.7	143.3	0.0	0.0	0.0	122.7	82.5	342.0	140.0	436.8
TOTALS	2743.9					1124.0				

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

PRE-STAGE & STAGE 3 PAVEMENT MARKING SCHEDULE (2 OF 2)

LOCATION	STAGE 3 PAVEMENT MARKINGS					
	78300200	70300510	70300520	70300540	70300570	
	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAVEMENT MARKING TAPE, TYPE III LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III			
			4"	6"	24"	
EACH	SQ FT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	
IL ROUTE 72						
STA 112+69.07 TO STA 124+33.29	17.0	182.0	0.0	3140.5	1555.2	112.0
IL ROUTE 31						
STA 203+19.37 TO STA 211+00.00	10.0	72.8	0.0	1862.4	741.2	0.0
STA 215+00.00 TO STA 223+07.84	8.0	109.2	0.0	1969.1	502.3	0.0
SUB TOTALS			0.0	6972.0		
TOTALS	35.0	364.0		6972.0	2798.7	112.0

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.