

**PRE-STAGE & STAGE 4 (FINAL) PAVEMENT MARKING SCHEDULE (1 OF 2)**

LOCATION	PRE-STAGE 4 REMOVALS			STAGE 4 TEMPORARY PAVEMENT MARKINGS												
	70301000			70300100		70300210	70300220	70300240	70300260	70300280						
	WORK ZONE PVMT MRKING REMOVAL			SHORT TERM PVMT MRKING		TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING LINE									
	4"	6"	24"	4"			4"	6"	12"	24"	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
SQ FT	SQ FT	SQ FT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
IL ROUTE 72																
STA 112+69.07 TO STA 118+50.00	1046.8	777.6	224.0	150.7	0.0	187.2	355.2	655.5	719.8	750.5	0.0	190.0				
STA 118+50.00 TO STA 124+33.29				134.7	23.0	72.8	437.1	361.4	361.4	0.0	23.0	32.1				
IL ROUTE 31																
STA 203+19.37 TO STA 209+00.00	620.8	370.6	0.0	139.2	0.0	72.8	194.9	911.1	456.2	0.0	0.0	31.8				
STA 209+00.00 TO STA 211+60.00				128.8	0.0	98.8	173.4	0.0	772.0	0.0	0.0	0.0				
STA 213+50.00 TO STA 215+00.00				60.0	0.0	41.6	100.0	0.0	299.9	0.0	0.0	0.0				
STA 215+00.00 TO STA 219+00.00	656.4	251.2	0.0	126.1	0.0	72.8	265.4	0.0	577.3	0.0	0.0	14.7				
STA 219+00.00 TO STA 223+07.84				61.5	7.6	109.2	399.9	224.7	338.5	0.0	73.7	14.6				
SUB TOTALS	2324.0	1399.3	224.0	800.9	30.6		1925.7	2152.7		720.5	96.7					
TOTALS		3947.3		831.5		655.2	4078.4	3525.1		817.2		283.2				

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

**PRE-STAGE & STAGE 4 (FINAL) PAVEMENT MARKING SCHEDULE (2 OF 2)**

LOCATION	STAGE 4 PERMANENT PAVEMENT MARKINGS															
	78000100	78000200	78000400	78000600	78000650	78000600										
	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING LINE							RAISED RELECTIVE PAVEMENT MARKER							
		4"	6"	12"	24"	WHITE	YELLOW	WHITE	ONE-WAY CRYSTAL EACH	ONE-WAY AMBER EACH	TWO-WAY AMBER EACH					
SQ FT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	FOOT	FOOT	FOOT	FOOT						
IL ROUTE 72																
STA 112+69.07 TO STA 118+50.00	187.2	355.2	655.5	719.8	720.5	0.0	190.0	33	0	0						
STA 118+50.00 TO STA 124+33.29	72.8	437.1	361.4	361.4	0.0	23.0	32.1	34	0	6						
IL ROUTE 31																
STA 203+19.37 TO STA 209+00.00	72.8	194.9	911.1	456.2	0.0	0.0	31.8	35	0	0						
STA 209+00.00 TO STA 211+60.00	98.8	173.4	0.0	772.0	0.0	0.0	0.0	35	0	0						
STA 213+50.00 TO STA 215+00.00	41.6	100.0	0.0	299.9	0.0	0.0	0.0	13	0	0						
STA 215+00.00 TO STA 219+00.00	72.8	265.4	0.0	577.3	0.0	0.0	14.7	32	0	0						
STA 219+00.00 TO STA 223+07.84	109.2	399.9	224.7	338.5	0.0	73.7	14.6	16	9	0						
SUB TOTALS		1925.7	2152.7		720.5	96.7		198	9	6						
TOTALS	655.2	4078.4	3525.1	817.2	283.2			213								

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED -
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = *SCALE*	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = *DATE*	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>	
SCALE: NONE	SHEET NO. 19 OF 25 SHEETS
STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	36
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				