

EXISTING SIGNING REMOVALS & RELOCATIONS (1 OF 3)

PANEL DESCRIPTION	EXISTING SIZES		EXISTING SIGN LOCATIONS			72400100	72400200	72400310	72400720
	WIDTH	HEIGHT	STATION	OFFSET	LT/RT	REMOVE SIGN PANEL ASSEMBLY - TY A	REMOVE SIGN PANEL ASSEMBLY - TY B	REMOVE SIGN PANEL TYPE 1	RELOCATE SIGN PANEL TYPE 2
	INCHES	INCHES				EACH	EACH	SQ FT	SQ FT
IL ROUTE 72									
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
STOP	30	30	113+42.98	41.65'	RT	1	-	-	-
STATE ROUTE	24	24	113+55.07	28.68'	RT	1	-	-	-
DIRECTIONAL ARROW	21	15	113+55.07	28.68'	RT	-	-	-	-
LAND OF LINCOLN (SALVAGE)	24	30	114+16.19	53.01'	LT	-	1	-	-
ADOPT A HIGHWAY (SALVAGE)	24	18	114+16.19	53.01'	LT	-	-	-	-
KEEP ILLINOIS CLEAN (SALVAGE)	36	36	114+16.19	53.01'	LT	-	-	-	-
WEST	24	12	115+01.29	46.67'	LT	-	-	2.0	-
STATE ROUTE	24	24	115+01.29	46.67'	LT	-	-	4.0	-
IL RT 31	60	30	ON EXIST TRAFFIC SIGNAL			-	-	-	12.5
DIRECTIONAL ARROW	21	15	115+46.02	68.84'	LT	-	-	2.2	-
STATE ROUTE	24	24	115+46.02	68.84'	LT	-	-	4.0	-
SCHOOL CROSSING	36	36	115+46.02	68.84'	LT	-	-	9.0	-
STOP	30	30	115+46.02	68.84'	LT	-	-	6.25	-
LEFT ON GREEN ARROW ONLY	24	30	-	-	-	-	-	-	-
SCHOOL CROSSING	36	36	115+36.18	36.16'	RT	-	-	9.0	-
STOP	30	30	115+36.18	36.16'	RT	-	-	6.25	-
IL RT 72	60	30	ON EXIST TRAFFIC SIGNAL			-	-	-	12.5
LEFT ON GREEN ARROW ONLY	-	-	-	-	-	-	-	-	-
PHOTO ENFORCED (SALVAGE)	24	24	116+34.60	71.67'	LT	1	-	-	-
SCHOOL CROSSING	36	36	116+47.37	50.75'	RT	-	-	9.0	-
STOP	30	30	116+47.37	50.75'	RT	-	-	6.25	-
IL RT 31	60	30	ON EXIST TRAFFIC SIGNAL			-	-	-	12.5
LEFT ON GREEN ARROW ONLY	-	-	-	-	-	-	-	-	-
"Eighth St." (SALVAGE)	8	36	116+50.13	48.24'	LT	1	-	-	-
"Main St." (SALVAGE)	8	36	116+50.13	48.24'	LT	-	-	-	-
IL RT 72	60	30	ON EXIST TRAFFIC SIGNAL			-	-	-	12.5
LEFT ON GREEN ARROW ONLY	-	-	-	-	-	-	-	-	-
SCHOOL CROSSING	36	36	116+55.21	43.21'	LT	-	-	9.0	-
STOP	30	30	116+55.21	43.21'	LT	-	-	6.25	-
STATE ROUTE	24	24	116+52.10	52.09'	RT	-	1	-	-
DIRECTIONAL ARROW	21	15	116+52.10	52.09'	RT	-	-	-	-
STATE ROUTE	24	24	116+76.83	28.60'	RT	-	-	4.0	-
SUB TOTALS						4	2	77.2	50.0



USER NAME = #USER#	DESIGNED <i>ESI</i>	REVISED -
DRAWN <i>ESI</i>	REVISED -	
PLOT SCALE = #SCALE#	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = #DATE#	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE	SHEET NO. 20 OF 25 SHEETS	STA.	TO STA.
-------------	---------------------------	------	---------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	37
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				