

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOSFL,01	LOSFL,01	LOSFL,02	LOSFL,03	LOSFL,04	LOSFL,05	OTPOL,01		
				CONSTRUCTION CODE FUNDS								
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY OF NAPERVILLE	
ROADWAY	RETAINING WALL SN 022-W043	RETAINING WALL SN 022-W044	RETAINING WALL SN 022-W046	RETAINING WALL SN 022-W042	RETAINING WALL SN 022-W052	RETAINING WALL SN 022-W052	ELECTRIC DUCT BANK					
0004	0040	0040	0040	0040	0040	0040	0043					
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN					
20101200	TREE ROOT PRUNING	EACH	10							10		
20200100	EARTH EXCAVATION	CU YD	560	560								
20400800	FURNISHED EXCAVATION	CU YD	3785	3785								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	56	56								
20800150	TRENCH BACKFILL	CU YD	1556	1556								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2280	2280								
25000210	SEEDING, CLASS 2A	ACRE	2.00	2.00								
25100115	MULCH, METHOD 2	ACRE	4.00	4.00								
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1230	1230								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	196	196								
28000305	TEMPORARY DITCH CHECKS	FOOT	30	30								
28000400	PERIMETER EROSION BARRIER	FOOT	2186	2186								
28000510	INLET FILTERS	EACH	39	39								
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	37	37								
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	50	5						45		

X SPECIALTY ITEM

FILE NAME	DIGER NAME / NUMBER	DESIGNED <i>NAV</i>	REVISED <i>06-04-12</i>	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE NO.	PLANT SCALE - AS SHOWN	DRAWN <i>KE'S</i>	REVISED					338	2011-036-I	DUPAGE	234	4
PLANT DATE - 10/11/11	CHECKED <i>PJO</i>	DATE <i>05-11-12</i>	REVISED		SCALE: AS SHOWN SHEET NO. 1 OF 10 SHEETS STA. TO STA.			CONTRACT NO. 60P42				
ILLINOIS FED. AID PROJECT												