ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

FILE NAME = $FILE$

USER NAME = $USER$

PLOT SCALE = $SCALE$

PLOT DATE = $DATE$

DESIGNED	- NAV	
DRAWN	- KES	
CHECKED	- PJO	
DATE	- 05-11-12	

REVISED	-	
REVISED	-	
REVISED	-	
REVISED	-	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SN 022-W042
CROSS-SECTIONS

SCALE: 1

SHEET NO. 1 OF 1 SHEETS STA. 3911+50 TO STA. 3913+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2011-036-I	DUPAGE	234	101

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

CONTRACT NO. 60P42

120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50

710 705 700 695 690

PROP. R.O.W.
EXIST. R.O.W.
6:1
2%
TEL-ATT
GAS
COMED

3913+00

	END-AREA	UNIT
EARTH EXCAVATION	3.6	SQ FT.
EMBANKMENT	0.0	SQ FT.
TOPSOIL EXC & PLAC	8.5	SQ FT.

697.80

3912+50

	END-AREA	UNIT
EARTH EXCAVATION	5.2	SQ FT.
EMBANKMENT	0.0	SQ FT.
TOPSOIL EXC & PLAC	9.4	SQ FT.

697.42

3912+00

	END-AREA	UNIT
EARTH EXCAVATION	6.8	SQ FT.
EMBANKMENT	0.0	SQ FT.
TOPSOIL EXC & PLAC	9.5	SQ FT.

696.63

3911+50

	END-AREA	UNIT
EARTH EXCAVATION	17.0	SQ FT.
EMBANKMENT	0.0	SQ FT.
TOPSOIL EXC & PLAC	12.2	SQ FT.

696.39